arXiv:hep-ph/0603079v1 9 Mar 2006

TUM-HEP-600/05
IPPP/05/74
DCPT/05/148
TTP06-06
FERMILAB-PUB-05-512-T
ZU-TH 23/05
hep-ph/0603079

February 2, 2008

Charm Quark Contribution to $K^+ \to \pi^+ \nu\bar{\nu}$ at Next-to-Next-to-Leading Order

Andrzej J. Buras[a], Martin Gorbahn[b,c], Ulrich Haisch[d,e] and Ulrich Nierste[c,d]

[a] *Physik Department, Technische Universität München, D-85748 Garching, Germany*

[b] *IPPP, Physics Department, University of Durham, DH1 3LE, Durham, UK*

[c] *Institut für Theoretische Teilchenphysik, Universität Karlsruhe, D-76128 Karlsruhe, Germany*

[d] *Theoretical Physics Department, Fermilab, Batavia, IL 60510, USA*

[e] *Institut für Theoretische Physik, Universität Zürich, CH-8057 Zürich, Switzerland*

Abstract

We calculate the complete next-to-next-to-leading order QCD corrections to the charm contribution of the rare decay $K^+ \to \pi^+\nu\bar{\nu}$. We encounter several new features, which were absent in lower orders. We discuss them in detail and present the results for the two-loop matching conditions of the Wilson coefficients, the three-loop anomalous dimensions, and the two-loop matrix elements of the relevant operators that enter the next-to-next-to-leading order renormalization group analysis of the Z-penguin and the electroweak box contribution. The inclusion of the next-to-next-to-leading order QCD corrections leads to a significant reduction of the theoretical uncertainty from $\pm 9.8\%$ down to $\pm 2.4\%$ in the relevant parameter $P_c(X)$, implying the leftover scale uncertainties in $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ and in the determination of $|V_{td}|$, $\sin 2\beta$, and γ from the $K \to \pi\nu\bar{\nu}$ system to be $\pm 1.3\%$, $\pm 1.0\%$, ± 0.006, and $\pm 1.2^\circ$, respectively. For the charm quark $\overline{\rm MS}$ mass $m_c(m_c) = (1.30 \pm 0.05)\,\text{GeV}$ and $|V_{us}| = 0.2248$ the next-to-leading order value $P_c(X) = 0.37 \pm 0.06$ is modified to $P_c(X) = 0.38 \pm 0.04$ at the next-to-next-to-leading order level with the latter error fully dominated by the uncertainty in $m_c(m_c)$. We present tables for $P_c(X)$ as a function of $m_c(m_c)$ and $\alpha_s(M_Z)$ and a very accurate analytic formula that summarizes these two dependences as well as the dominant theoretical uncertainties. Adding the recently calculated long-distance contributions we find $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu}) = (8.0 \pm 1.1) \times 10^{-11}$ with the present uncertainties in $m_c(m_c)$ and the Cabibbo-Kobayashi-Maskawa elements being the dominant individual sources in the quoted error. We also emphasize that improved calculations of the long-distance contributions to $K^+ \to \pi^+\nu\bar{\nu}$ and of the isospin breaking corrections in the evaluation of the weak current matrix elements from $K^+ \to \pi^0 e^+ \nu$ would be valuable in order to increase the potential of the two golden $K \to \pi\nu\bar{\nu}$ decays in the search for new physics.

1 Introduction

The rare decay $K^+ \to \pi^+\nu\bar{\nu}$ plays together with $K_L \to \pi^0\nu\bar{\nu}$ an outstanding role in the field of flavor changing neutral current (FCNC) processes both in the standard model (SM) [1] and in all of its extensions [2,3]. The main reason for this is its theoretical cleanness and its large sensitivity to short-distance QCD effects that can be systematically calculated using an effective field theory framework. The hadronic matrix element of this decay can be extracted, including isospin breaking corrections [4], from the accurately measured leading semileptonic decay $K^+ \to \pi^0 e^+ \nu$, and the remaining long-distance contributions [5] turn out to be small [6], and in principle calculable by means of lattice QCD [7].

Consequently the SM decay rate of $K^+ \to \pi^+\nu\bar{\nu}$ can be expressed almost entirely in terms of the Cabibbo-Kobayashi-Maskawa (CKM) [8] parameters, the top and the charm quark mass, and the strong coupling constant $\alpha_s(M_Z)$ that enters the QCD corrections calculated within renormalization group (RG) improved perturbation theory. Beyond the SM additional parameters like new couplings and masses of new heavy particles will be present in the decay rate, but from the point of view of hadronic effects, the theoretical cleanness of the prediction will not be affected by these non-standard contributions.

In view of this, the theoretical uncertainties in the decay rate of $K^+ \to \pi^+\nu\bar{\nu}$ are at leading order essentially only of perturbative origin and in order to be able to test the SM and its extensions to a high degree of precision it is important to evaluate the first non-trivial and higher order QCD corrections to this decay mode.

To be specific, the low-energy effective Hamiltonian for the $K \to \pi\nu\bar{\nu}$ system can be written in the SM as follows [9, 10]

$$\mathcal{H}_{\text{eff}} = \frac{4G_F}{\sqrt{2}} \frac{\alpha}{2\pi \sin^2\theta_W} \sum_{\ell=e,\mu,\tau} \left(\lambda_c X^\ell(x_c) + \lambda_t X(x_t)\right) (\bar{s}_L \gamma_\mu d_L)(\bar{\nu}_{\ell L} \gamma^\mu \nu_{\ell L})\,. \tag{1}$$

Here G_F, α, and $\sin^2\theta_W$ denote the Fermi constant, the electromagnetic coupling, and the weak mixing angle, respectively. The sum over ℓ extends over all lepton flavors, $\lambda_i = V_{is}^* V_{id}$ are the relevant CKM factors and f_L are left-handed fermion fields. The dependence on the charged lepton mass is negligible for the top quark contribution. In the charm quark sector this is the case only for the electron and the muon but not for the tau lepton.

The function $X(x_t)$ in Eq. (1) depends on the top quark $\overline{\text{MS}}$ [11] mass through $x_t = m_t^2(\mu_t)/M_W^2$. It originates from Z-penguin and electroweak box diagrams with an internal top quark. Sample diagrams are shown in Fig. 1. As the relevant operator has a vanishing anomalous dimension and the energy scales involved are of the order of the electroweak scale or higher, the function $X(x_t)$ can be calculated within ordinary perturbation theory. It is known through next-to-leading order (NLO) [10, 12, 13]. The inclusion of these $\mathcal{O}(\alpha_s)$ corrections allowed to reduce the $\pm 6\%$ uncertainty due to the top quark matching scale $\mu_t = \mathcal{O}(m_t)$ present in the leading order (LO) formula down to $\pm 1\%$. Consequently the reached theoretical accuracy on the top quark contribution to $K^+ \to \pi^+\nu\bar{\nu}$ and in the



Figure 1: Examples of Z-penguin and electroweak box diagrams that contribute both to $K^+ \to \pi^+\nu\bar{\nu}$ and $K_L \to \pi^0\nu\bar{\nu}$. Here and in the following we do not display the neutrino line attached to the Z-boson.

amplitude of $K_L \to \pi^0\nu\bar{\nu}$, where only $X(x_t)$ enters, is satisfactory.

The function $X^\ell(x_c)$ in Eq. (1) relevant only for $K^+ \to \pi^+\nu\bar{\nu}$ depends on the charm quark $\overline{\rm MS}$ mass through $x_c = m_c^2(\mu_c)/M_W^2$. As now both high- and low-energy scales, namely $\mu_W = \mathcal{O}(M_W)$ and $\mu_c = \mathcal{O}(m_c)$ are involved, a complete RG analysis of this term is required. In this manner, large logarithms $\ln(\mu_c^2/\mu_W^2)$ are resummed to all orders in α_s. At LO such an analysis has been performed in [14]. The large scale uncertainty due to μ_c of $\pm 26\%$ in this result was a strong motivation for the NLO analysis of this contribution [9,10].

Defining the phenomenologically useful parameter

$$P_c(X) = \frac{1}{\lambda^4}\left(\frac{2}{3}X^e(x_c) + \frac{1}{3}X^\tau(x_c)\right), \tag{2}$$

with $\lambda = |V_{us}|$, one finds for $\lambda = 0.2248$ at NLO [15][1]

$$P_c(X) = 0.369 \pm 0.036_{\rm theory} \pm 0.033_{m_c} \pm 0.009_{\alpha_s}, \tag{3}$$

where the parametric errors correspond to the ranges of the charm quark $\overline{\rm MS}$ mass $m_c(m_c)$ and the strong coupling constant $\alpha_s(M_Z)$ given in Tab. 4. The theoretical error summarizes uncertainties due to various scales and different methods of computing $\alpha_s(\mu_c)$ from $\alpha_s(M_Z)$. Details on how the quoted errors have been obtained will be given in Sec. 9.

Provided $P_c(X)$ is known with a sufficient precision, a measurement of $K^+ \to \pi^+\nu\bar{\nu}$, either alone or together with one of $K_L \to \pi^0\nu\bar{\nu}$, allows for precise determinations of the CKM parameters [1]. The comparison of this standard unitarity triangle (UT) with the one from B-physics offers a stringent and unique test of the SM. In particular for the branching ratios $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ and $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$ close to their SM predictions, one finds that a

[1] The numerical results presented here differ somewhat from [15]. For the present numerical evaluation the program used in [15] has been changed slightly in order to implement the various theoretical errors in an improved fashion.

given uncertainty $\sigma(P_c(X))$ translates into [15]

$$\begin{aligned}
\frac{\sigma\left(|V_{td}|\right)}{|V_{td}|} &= \pm 0.41\,\frac{\sigma\left(P_c(X)\right)}{P_c(X)}\,,\\
\frac{\sigma\left(\sin 2\beta\right)}{\sin 2\beta} &= \pm 0.34\,\frac{\sigma\left(P_c(X)\right)}{P_c(X)}\,,\\
\frac{\sigma\left(\gamma\right)}{\gamma} &= \pm 0.83\,\frac{\sigma\left(P_c(X)\right)}{P_c(X)}\,,
\end{aligned} \tag{4}$$

with similar formulas given in [3]. Here V_{td} is the element of the CKM matrix and β and γ are the angles in the standard UT. As the uncertainties in Eq. (3) coming from the charm quark mass and the CKM parameters should be decreased in the coming years it is also desirable to reduce the theoretical uncertainty in $P_c(X)$.

To this end, we extend here the NLO analysis of $P_c(X)$ presented in [9,10] to the next-to-next-to-leading order (NNLO) [15]. We encounter several new features, which were absent in lower orders. First, closed quark loops in gluon propagators occur, resulting in a novel dependence of $P_c(X)$ on the top quark mass and in non-trivial matching corrections at the bottom quark threshold scale $\mu_b = \mathcal{O}(m_b)$. Second, the contributions from the vector component of the Z-boson coupling are non-trivial at NNLO and are only found to vanish in the sum of several contributions, which involve a flavor off-diagonal wave function renormalization. Third, the presence of anomalous triangle diagrams involving a top quark loop, two gluons, and a Z-boson makes it necessary to introduce a Chern-Simons operator [16, 17] in order to obtain the correct anomalous Ward identity of the axial-vector current [18]. The inclusion of such a Chern-Simons term is also required to compensate for the anomalous contributions from triangle diagrams with a bottom quark loop. Since all these effects arise first at NNLO, they are not included in the theoretical uncertainty quoted in Eq. (3), which has been estimated from the variation of scales and different methods of evaluating $\alpha_s(\mu_c)$ from $\alpha_s(M_Z)$. The only way to control their size is to compute them explicitly, which is a further strong motivation for our NNLO calculation.

Our paper is organized as follows. In Sec. 2 we give formulas for $P_c(X)$ and $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ at NNLO in a form suitable for phenomenological applications. In particular we present tables that show $P_c(X)$ for different values of $\alpha_s(M_Z)$, μ_c, and $m_c(m_c)$ and we give a simple analytic formula for $P_c(X)$ that approximates the exact numerical result with high accuracy. Sec. 3 is meant to be a guide to the subsequent Secs. 4 to 7 that describe our calculation in detail. These sections are naturally rather technical and might be skipped by readers mainly interested in phenomenological applications of our result. Sec. 8 contains another accurate approximate formula for $P_c(X)$ that summarizes the dominant parametric and theoretical uncertainties. In Sec. 9 we present the numerical analysis of the NNLO formulas. In particular we analyze various scale uncertainties that are drastically reduced by going from NLO to NNLO. We present the result for $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ and $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$ and we investigate the parametric and theoretical uncertainties in the determination of the

CKM parameters with the latter being significantly reduced through our calculation. In the course of this section we also present results provided by the CKMfitter Group [19] and the **UT***fit* Collaboration [20]. We conclude in Sec. 10. Some technical details as well as additional material has been relegated to the appendices.

2 Master Formulas at NNLO

2.1 Preliminaries

In this section we will present the formula for $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ based on the low-energy effective Hamiltonian given in Eq. (1) extended to include the recently calculated contributions of dimension-eight four fermion operators generated at the charm quark scale μ_c, and of genuine long-distance contributions which can be described within the framework of chiral perturbation theory [6]. These contributions can be effectively included by adding

$$\delta P_{c,u} = 0.04 \pm 0.02\,, \tag{5}$$

to the relevant parameter $P_c(X)$. The quoted error in $\delta P_{c,u}$ can in principle be reduced by means of lattice QCD [7].

For completeness we will also recall the formula for $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$ which we will use in Sec. 9 to obtain its updated SM value in view of the recently modified value of the top quark mass [21].

2.2 Branching Ratio for $K^+ \to \pi^+\nu\bar{\nu}$

After summation over the three neutrino flavors the resulting branching ratio for $K^+ \to \pi^+\nu\bar{\nu}$ can be written as [6, 9, 10]

$$\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu}) = \kappa_+ \left[\left(\frac{\mathrm{Im}\lambda_t}{\lambda^5} X(x_t) \right)^2 + \left(\frac{\mathrm{Re}\lambda_t}{\lambda^5} X(x_t) + \frac{\mathrm{Re}\lambda_c}{\lambda} \left(P_c(X) + \delta P_{c,u} \right) \right)^2 \right], \tag{6}$$

with

$$\kappa_+ = r_{K^+} \frac{3\alpha^2\, \mathcal{B}(K^+ \to \pi^0 e^+ \nu)}{2\pi^2 \sin^4\theta_W} \lambda^8 = (5.04 \pm 0.17) \times 10^{-11} \left(\frac{\lambda}{0.2248} \right)^8 . \tag{7}$$

Here the parameter $r_{K^+} = 0.901 \pm 0.027$ summarizes isospin breaking corrections in relating $K^+ \to \pi^+\nu\bar{\nu}$ to $K^+ \to \pi^0 e^+ \nu$ [4]. The apparent strong dependence of $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ on λ is spurious as both $P_c(X)$ and $\delta P_{c,u}$ are proportional to $1/\lambda^4$. In quoting the value for $P_c(X)$ and $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ we will set $\lambda = 0.2248$. α and $\sin^2\theta_W$ entering $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ are naturally evaluated at the electroweak scale [22]. Then the leading term in the heavy top expansion of the electroweak two-loop corrections to $X(x_t)$ amounts to typically -1%

for the $\overline{\rm MS}$ definition of α and $\sin^2\theta_W$ [23]. In obtaining the numerical value of Eq. (7) we have employed $\alpha = \alpha_{\overline{\rm MS}}(M_Z) = 1/127.9$, $\sin^2\theta_W = \sin^2\hat{\theta}_W = 0.231$, and $\mathcal{B}(K^+ \to \pi^0 e^+ \nu) = (4.93 \pm 0.07) \times 10^{-2}$ [24]. We remark that in writing $\mathcal{B}(K^+ \to \pi^+ \nu\bar{\nu})$ in the form of Eq. (6) we have omitted a term proportional to $(X^e(x_c) - X^\tau(x_c))^2$. Its effect on $\mathcal{B}(K^+ \to \pi^+ \nu\bar{\nu})$ is around $+0.2\%$.

The function $X(x_t)$ entering Eqs. (1), (6) and (17) is given in NLO accuracy by

$$X(x_t) = X_0(x_t) + \frac{\alpha_s(\mu_t)}{4\pi} X_1(x_t) = \eta_X X_0(x_t(m_t))\,, \tag{8}$$

with

$$\eta_X = 0.986 \pm 0.009\,. \tag{9}$$

The contribution stemming from Z-penguin and electroweak box diagrams without QCD corrections reads [25]

$$X_0(x_t) = -\frac{2x_t + x_t^2}{8(1-x_t)} - \frac{6x_t - 3x_t^2}{8(1-x_t)^2}\ln x_t\,, \tag{10}$$

while the QCD corrections to it take the following form [10, 12, 13]

$$\begin{aligned} X_1(x_t) = &-\frac{29x_t - x_t^2 - 4x_t^3}{3(1-x_t)^2} - \frac{x_t + 9x_t^2 - x_t^3 - x_t^4}{(1-x_t)^3}\ln x_t \\ &+ \frac{8x_t + 4x_t^2 + x_t^3 - x_t^4}{2(1-x_t)^3}\ln^2 x_t - \frac{4x_t - x_t^3}{(1-x_t)^2}{\rm Li}_2(1-x_t) + 8x_t\frac{\partial X_0(x_t)}{\partial x_t}\ln\frac{\mu_t^2}{M_W^2}\,. \end{aligned} \tag{11}$$

Here ${\rm Li}_2(x) = -\int_0^x dt\, \ln(1-t)/t$. The explicit μ_t-dependence of the last term in Eq. (11) cancels to the considered order the μ_t-dependence of the leading term $X_0(x_t(\mu_t))$. The factor η_X summarizes the NLO corrections. Its error has been obtained by varying μ_t in the range $60\,{\rm GeV} \le \mu_t \le 240\,{\rm GeV}$ on the left-hand side of Eq. (8) while keeping μ_t fixed at $m_t = m_t(m_t)$ on the right-hand side of the same equation. The leftover μ_t-dependence in $X(x_t)$ is slightly below $\pm 1\%$.

The uncertainty in $X(x_t)$ is then dominated by the experimental error in the mass of the top quark. Converting the top quark pole mass of $M_t = (172.7 \pm 2.9)\,{\rm GeV}$ [21] at three loops to $m_t(M_t)$ [26] and relating $m_t(M_t)$ to $m_t(m_t) = (163.0 \pm 2.8)\,{\rm GeV}$ using one-loop accuracy, we find

$$X(x_t) = 1.464 \pm 0.041\,. \tag{12}$$

The given uncertainty combines linearly an error of ± 0.028 due to the error of $m_t(m_t)$ and an error of ± 0.013 obtained by varying μ_t in the range given above.

As opposed to $X(x_t)$ the charm quark contribution, represented by the parameter $P_c(X)$ in Eq. (2), involves several different scales like μ_W, μ_b, and μ_c. In order to control the size of the perturbative corrections to $P_c(X)$ the large logarithms associated with these scales



Figure 2: The parameter $P_c(X)$ at NNLO as a function of $m_c(m_c)$ (upper plot) and $\alpha_s(M_Z)$ (lower plot). In obtaining the numerical values for $P_c(X)$ we have set $\lambda = 0.2248$, $m_t(m_t) = 163.0\,\text{GeV}$, $\mu_W = 80.0\,\text{GeV}$, $\mu_b = 5.0\,\text{GeV}$, $\mu_c = 1.50\,\text{GeV}$, $\alpha_s(M_Z) = 0.1187$ (upper plot), and $m_c(m_c) = 1.30\,\text{GeV}$ (lower plot).

	$P_c(X)$				
$\alpha_s(M_Z)$ \ μ_c [GeV]	1.0	1.5	2.0	2.5	3.0
0.115	0.393	0.397	0.395	0.392	0.388
0.116	0.389	0.394	0.391	0.388	0.383
0.117	0.384	0.390	0.387	0.383	0.379
0.118	0.380	0.386	0.383	0.379	0.374
0.119	0.375	0.381	0.379	0.374	0.369
0.120	0.370	0.377	0.374	0.369	0.364
0.121	0.365	0.372	0.369	0.364	0.359
0.122	0.359	0.368	0.364	0.359	0.354
0.123	0.353	0.363	0.359	0.354	0.348

Table 1: The parameter $P_c(X)$ in NNLO approximation for various values of $\alpha_s(M_Z)$ and μ_c. In quoting the numerical values for $P_c(X)$ we have set $\lambda = 0.2248$, $m_t(m_t) = 163.0\,\text{GeV}$, $m_c(m_c) = 1.30\,\text{GeV}$, $\mu_W = 80.0\,\text{GeV}$, and $\mu_b = 5.0\,\text{GeV}$.

have to be resummed to all orders in α_s using RG techniques. Keeping terms to first order in α_s, the perturbative expansion of $P_c(X)$ has the following general structure

$$P_c(X) = \frac{4\pi}{\alpha_s(\mu_c)} P_c^{(0)}(X) + P_c^{(1)}(X) + \frac{\alpha_s(\mu_c)}{4\pi} P_c^{(2)}(X)\,, \tag{13}$$

where we have suppressed the dependence of the expansion coefficients $P_c^{(k)}(X)$ on the involved physical and unphysical mass scales for simplicity. The leading term $P_c^{(0)}(X)$ has been worked out in [14] while the NLO correction $P_c^{(1)}(X)$ has been calculated in [9, 10].

The main goal of the present paper is the calculation of the NNLO term $P_c^{(2)}(X)$. As indicated by the theoretical error in Eq. (3), the sum of the first two terms in Eq. (13) still exhibits sizable unphysical scale dependences, in particular the one on μ_c. Besides, the NLO value of $P_c(X)$ depends in a non-negligible way on the method used to compute $\alpha_s(\mu_c)$ from $\alpha_s(M_Z)$ [15]. The observed numerical difference is due to higher order terms in α_s and has to be regarded as part of the theoretical error. This source of uncertainty has not been taken into account in previous NLO analyses of the charm quark contribution [3, 9, 10].

As we will demonstrate in Sec. 9, the inclusion of $P_c^{(2)}(X)$ removes essentially the entire sensitivity of $P_c(X)$ on μ_c and on higher order terms in α_s that effect the evaluation of $\alpha_s(\mu_c)$ from $\alpha_s(M_Z)$. As a result, the final theoretical error in $P_c(X)$ is reduced from $\pm 9.8\%$ at NLO down to $\pm 2.4\%$ at NNLO. After our calculation the theoretical accuracy on the charm quark contribution to $K^+ \to \pi^+ \nu\bar{\nu}$ is thus also satisfactory.

	$P_c(X)$						
$\alpha_s(M_Z)$ \ $m_c(m_c)$ [GeV]	1.15	1.20	1.25	1.30	1.35	1.40	1.45
0.115	0.307	0.336	0.366	0.397	0.430	0.463	0.497
0.116	0.303	0.332	0.362	0.394	0.426	0.459	0.493
0.117	0.300	0.329	0.359	0.390	0.422	0.455	0.489
0.118	0.296	0.325	0.355	0.386	0.417	0.450	0.484
0.119	0.292	0.321	0.350	0.381	0.413	0.446	0.480
0.120	0.288	0.316	0.346	0.377	0.409	0.441	0.475
0.121	0.283	0.312	0.342	0.372	0.404	0.437	0.470
0.122	0.279	0.307	0.337	0.368	0.399	0.432	0.465
0.123	0.274	0.303	0.332	0.363	0.394	0.426	0.460

Table 2: The parameter $P_c(X)$ in NNLO approximation for various values of $\alpha_s(M_Z)$ and $m_c(m_c)$. In quoting the numerical values for $P_c(X)$ we have set $\lambda = 0.2248$, $m_t(m_t) = 163.0\,\text{GeV}$, $\mu_W = 80.0\,\text{GeV}$, $\mu_b = 5.0\,\text{GeV}$, and $\mu_c = 1.50\,\text{GeV}$.

The analytic formula for the sum of the first two terms in Eq. (13) can be found in [9,10]. The formula for $P_c^{(2)}(X)$ is given in Secs. 6 to 8. Setting $\lambda = 0.2248$, $m_t(m_t) = 163.0\,\text{GeV}$, $\mu_W = 80.0\,\text{GeV}$, $\mu_b = 5.0\,\text{GeV}$, and $\mu_c = 1.50\,\text{GeV}$, we derive an approximate formula for $P_c(X)$ as a function of $m_c(m_c)$ and $\alpha_s(M_Z)$. It reads

$$P_c(X) = 0.379 \left(\frac{m_c(m_c)}{1.30\,\text{GeV}}\right)^{2.155} \left(\frac{\alpha_s(M_Z)}{0.1187}\right)^{-1.417}, \tag{14}$$

and approximates the exact NNLO result with an accuracy of better than $\pm 1.0\%$ in the ranges $1.15\,\text{GeV} \le m_c(m_c) \le 1.45\,\text{GeV}$ and $0.1150 \le \alpha_s(M_Z) \le 0.1230$.

The dependence of $P_c(X)$ on $m_c(m_c)$ and $\alpha_s(M_Z)$ can be seen in Fig. 2, while in Tabs. 1 and 2 we present the exact values for $P_c(X)$ for different values of $\alpha_s(M_Z)$, μ_c, and $m_c(m_c)$. We observe that the μ_c-dependence is almost negligible and the dependence on $\alpha_s(M_Z)$ is small. On the other hand the dependence on $m_c(m_c)$ is sizable. A reduction of the error in $m_c(m_c)$, which is dominated by theoretical uncertainties, is thus an important goal in connection with $K^+ \to \pi^+\nu\bar{\nu}$.

Employing the central values of the input parameters summarized in Tab. 4, the dependence of $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ on $m_c(m_c)$ is described by

$$\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu}) = 8.15 \left(\frac{m_c(m_c)}{1.30\,\text{GeV}}\right)^{1.19} \times 10^{-11}, \tag{15}$$



Figure 3: The branching ratio $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ at NNLO as a function of $m_c(m_c)$ (upper plot) and M_t (lower plot). In obtaining the numerical values for $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ we have used $\mu_W = 80.0\,\text{GeV}$, $\mu_b = 5.0\,\text{GeV}$, and $\mu_c = 1.50\,\text{GeV}$, and set all input parameters to their central values as given in Tab. 4.

which approximates the exact NNLO result with an accuracy of almost $\pm 0.6\%$ in the range $1.15\,\text{GeV} \leq m_c(m_c) \leq 1.45\,\text{GeV}$. Similarly, the dependence on M_t is given by

$$\mathcal{B}(K^+ \to \pi^+ \nu\bar{\nu}) = 8.11 \left(\frac{M_t}{172.7\,\text{GeV}}\right)^{1.46} \times 10^{-11}\,, \tag{16}$$

which approximates the exact NNLO result with an accuracy of better than $\pm 0.1\%$ in the range $165.0\,\text{GeV} \leq M_t \leq 180.0\,\text{GeV}$. The dependences in Eqs. (15) and (16) are exhibited in Fig. 3. We remark that the present analysis of the UT is practically independent of the exact value of the top quark mass. In obtaining both Eqs. (15) and (16) we have therefore set for simplicity $\text{Im}\lambda_t$, $\text{Re}\lambda_t$, and $\text{Re}\lambda_c$ to their central values as given in Tab. 4. Furthermore we have used the numerical value of $P_c(X)$ evaluated at $\mu_W = 80.0\,\text{GeV}$, $\mu_b = 5.0\,\text{GeV}$, and $\mu_c = 1.5\,\text{GeV}$. A detailed numerical analysis of various uncertainties in $\mathcal{B}(K^+ \to \pi^+ \nu\bar{\nu})$ will be presented in Sec. 9.

2.3 Branching Ratio for $K_L \to \pi^0 \nu\bar{\nu}$

In the case of $K_L \to \pi^0 \nu\bar{\nu}$ the charm quark contribution and the long-distance effects are negligible so that the relevant branching ratio is given simply as follows [9, 10]

$$\mathcal{B}(K_L \to \pi^0 \nu\bar{\nu}) = \kappa_L \left(\frac{\text{Im}\lambda_t}{\lambda^5} X(x_t)\right)^2\,, \tag{17}$$

where

$$\kappa_L = \kappa_+ \frac{r_{K_L}}{r_{K^+}} \frac{\tau(K_L)}{\tau(K^+)} = (2.20 \pm 0.07) \times 10^{-10} \left(\frac{\lambda}{0.2248}\right)^8\,. \tag{18}$$

Here we have summed over the three neutrino flavors and used $\tau(K_L)/\tau(K^+) = 4.16 \pm 0.04$ [24]. $r_{K_L} = 0.944 \pm 0.028$ is the isospin breaking correction from [4] with κ_+ given in Eq. (7). Due to the absence of $P_c(X)$ in Eq. (17), $\mathcal{B}(K_L \to \pi^0 \nu\bar{\nu})$ is plagued only by small theoretical uncertainties coming from μ_t and κ_L. The total parametric uncertainty stemming from $m_t(m_t)$ and $\text{Im}\lambda_t$ is on the other hand sizeable. The latter errors should be decreased significantly in the coming years, so that a precise prediction for $\mathcal{B}(K_L \to \pi^0 \nu\bar{\nu})$ should be possible in this decade.

2.4 Summary

As far as perturbative uncertainties are concerned, with the NNLO correction to the charm quark contribution to $\mathcal{B}(K^+ \to \pi^+ \nu\bar{\nu})$ at hand, $K^+ \to \pi^+ \nu\bar{\nu}$ has been put nearly on the same level as $K_L \to \pi^0 \nu\bar{\nu}$. The leftover scale ambiguities are all small, so that the reached theoretical accuracy is now satisfactory in both decays. Similarly the errors due to uncertainties in $\alpha_s(M_Z)$ and $m_t(m_t)$ are small. The future of precise predictions for

$\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ will depend primarily on the reduction of the errors in $m_c(m_c)$ and in the CKM parameters, whereas $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$ is practically only affected by the uncertainties in the CKM elements. Non-negligible uncertainties arise in both cases also from the theoretical error of the isospin breaking corrections and in the case of $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ from the uncertainty associated with the long-distance corrections.

On the other hand the determination of the CKM parameters and of the UT from the $K \to \pi\nu\bar{\nu}$ system will depend on the progress in the determination of $m_c(m_c)$ and the measurements of both branching ratios. Also a further reduction of the error in $|V_{cb}|$, r_{K^+}, r_{K_L}, and $\delta P_{c,u}$ would be very welcome in this respect.

3 Guide to the NNLO Calculation

In analogy to many other FCNC processes, perturbative QCD effects lead to a sizable modification of the purely electroweak contribution to $K^+ \to \pi^+\nu\bar{\nu}$ by generating large logarithms of the form $L = \ln(\mu_c^2/\mu_W^2)$. A suitable framework to achieve the necessary resummation of the logarithmic enhanced corrections is the construction of an effective field theory by integrating out the heavy degrees of freedom. In this context short-distance QCD corrections can be systematically calculated by solving the RG equation that governs the scale dependence of the Wilson coefficient functions of the relevant local operators built out of the light and massless SM fields.

As several new features, which were absent in LO and NLO, enter the RG analysis of $P_c(X)$ at NNLO, the actual calculation is rather involved and it is worthwhile to outline first its general structure. This will be done in this section, whereas the details of the computation of the different ingredients that are necessary to obtain the NNLO correction to $P_c(X)$ will be described in Secs. 4 to 7.

The key element of the RG analysis of the charm quark contribution to the $s \to d\nu\bar{\nu}$ transition is the mixing of the bilocal composite operators

$$Q_\pm^P = -i \int d^4x \, T\big(Q_\pm^c(x) Q_Z(0) - Q_\pm^u(x) Q_Z(0)\big)\,, \tag{19}$$

and

$$Q^B = -i \int d^4x \, T\big(Q_3^c(x) Q_4^c(0) - Q_3^u(x) Q_4^u(0)\big)\,, \tag{20}$$

where T denotes the usual time-ordering, into

$$Q_\nu = \frac{m_c^2}{g^2 \mu^{2\epsilon}} \sum_{\ell=e,\mu,\tau} (\bar{s}_L \gamma_\mu d_L)\,(\bar{\nu}_{\ell L} \gamma^\mu \nu_{\ell L})\ . \tag{21}$$

Here m_c is the charm quark $\overline{\rm MS}$ mass $m_c(\mu)$, and the inverse powers of g have been introduced for later convenience, following [9]. One may arbitrarily shift such factors from



Figure 4: One-loop diagrams in the low-energy effective theory that involve a large leading logarithms. The black squares represent the insertion of the bilocal composite operators $Q_\pm^P$ (left) and Q^B (right). The charm quark line is open in the left diagram and in all subsequent diagrams in which the charm quark couples to $Q_\pm^c$.

the Wilson coefficient into the definition of the operator. The factor $\mu^{-2\epsilon}$ stems from the relation $g_0 = Z_g g \mu^\epsilon$, where Z_g denotes the renormalization constant of g, and the fact that Q_ν written in terms of bare fields and parameters must be μ-independent. All bare quantities will carry the subscript 0 hereafter. The operators $Q_\pm^q$, Q_3^q, and Q_4^q entering Eqs. (19) and (20) will be defined as we proceed.

Interestingly the charm quark contribution to the $s \to d\nu\bar{\nu}$ amplitude involves large logarithms even in the absence of QCD interactions, because $Q_\pm^P$ and Q^B mix into Q_ν through one-loop diagrams containing no gluon. The relevant Feynman graphs can be seen in Fig. 4. Factoring out G_F and α the charm quark contribution to the $s \to d\nu\bar{\nu}$ amplitude thus receives corrections of $\mathcal{O}(\alpha_s^n L^{n+1})$ at LO, of $\mathcal{O}(\alpha_s^n L^n)$ at NLO, and of $\mathcal{O}(\alpha_s^n L^{n-1})$ at NNLO. This structure of large logarithms explains the peculiar expansion of $P_c(X)$ in Eq. (13) with the leading term being of $\mathcal{O}(1/\alpha_s)$ rather than $\mathcal{O}(1)$.

Since there is no mixing between the bilocal composite operators $Q_\pm^P$ and Q^B, the RG analysis of $P_c(X)$ naturally splits into two parts: one for the Z-penguin contribution which involves $Q_\pm^P$ and one for the electroweak box contribution that brings Q^B into play. As the structure of the Z-penguin is more complicated than the one of the electroweak boxes it is useful to discuss the former type of contributions first. This will be done in Sec. 6. After the detailed exposition of the Z-penguin contribution it is straightforward to repeat the analysis in the analogous, but somewhat simpler case of the electroweak boxes. The essential steps of this calculation will be discussed in Sec. 7.

The main components of the calculations of Secs. 6 and 7 performed here at the NNLO level are: *i*) the two-loop $\mathcal{O}(\alpha_s^2)$ corrections to the initial conditions of the relevant Wilson coefficients at μ_W, *ii*) the three-loop $\mathcal{O}(\alpha_s^3)$ ADM describing the mixing of the associated physical operators, *iii*) the two-loop $\mathcal{O}(\alpha_s^2)$ threshold corrections to the Wilson coefficients at μ_b, and *iv*) the two-loop matrix elements $\mathcal{O}(\alpha_s^2)$ of the relevant operators at μ_c.

The current-current operators $Q_\pm^q$ which enters the bilocal composite operator $Q_\pm^P$ are

familiar from the non-leptonic $|\Delta S| = 1$ transitions. As their mixing under renormalization is not affected by the presence of the other operators, it is convenient to perform their RG analysis before discussing the Z-penguin contribution itself. This calculation involves the first three aforementioned steps as we will explain in Sec. 4.

The second ingredient of the bilocal composite operator $Q_\pm^P$ is the neutral-current operator Q_Z, which describes the interactions of neutrinos and quarks mediated by Z-boson exchange. It is a linear combination of the usual vector and axial-vector couplings of the left-handed neutrino current to quarks, and a Chern-Simons operator that describes the coupling of neutrinos to two and three gluons. The inclusion of the Chern-Simons operator is essential to guarantee the non-renormalization of Q_Z to all orders in α_s, which plays an important role in the RG analysis of the Z-penguin sector. The subleties arising in connection with Q_Z will be reviewed in Sec. 5.1 before analyzing the Z-penguin contribution itself.

Finally, we will discuss the operators Q_3^q and Q_4^q. These operators are the building blocks of the bilocal composite operator Q^B and describe the interactions between leptons and quarks mediated by W-exchange. They will be briefly discussed in Sec. 5.2.

In summary, after the three preparatory sections, namely Secs. 4, 5.1, and 5.2, that discuss the dimension-six operators $Q_\pm^q$, Q_Z, Q_3^q, and Q_4^q, the actual NNLO calculation relevant for the charm quark contribution to $K^+ \to \pi^+\nu\bar{\nu}$ is presented in Secs. 6 and 7 for the Z-penguin and the electroweak box contributions, respectively. The result of these efforts will be summarized in Sec. 8.

4 Current-Current Interactions

4.1 Effective Hamiltonian

As we are only interested in the charm quark contribution to the $s \to d\nu\bar{\nu}$ transition, we can drop the parts of the low-energy effective Hamiltonian that are proportional to the CKM factor λ_t. The unitarity of the CKM matrix then allows one to express all the relevant contributions in terms of one independent CKM factor, namely λ_c. $P_c(X)$ receives contributions from Z-penguin and electroweak box diagrams with internal charm and up quarks. Examples are depicted in Fig. 1. For scales μ in the range $\mu_c \le \mu \le \mu_W$ the four-quark interaction mediated by W-boson exchange is described by the effective current-current Hamiltonian

$$\mathcal{H}_{\text{eff}}^{CC} = \frac{4G_F}{\sqrt{2}}\lambda_c \sum_{i=\pm} C_i(\mu)\,(Q_i^c - Q_i^u)\ , \tag{22}$$

where

$$Q_\pm^q = \frac{1}{2}\left((\bar{s}_L^\alpha\gamma_\mu q_L^\alpha)(\bar{q}_L^\beta\gamma^\mu d_L^\beta) \pm (\bar{s}_L^\alpha\gamma_\mu q_L^\beta)(\bar{q}_L^\beta\gamma^\mu d_L^\alpha)\right)\ . \tag{23}$$



Figure 5: Sample diagrams for the $\mathcal{O}(\alpha_s^2)$ corrections to the initial values of the Wilson coefficients of the current-current operators.

Here α and β are color indices. At LO the operators in Eq. (23) renormalize multiplicatively. Beyond LO they mix into so-called evanescent operators, which vanish algebraically in $n = 4$ dimensions [27–30], but affect the values of the Wilson coefficients $C_\pm(\mu)$. These operators can be chosen in such a way that the renormalized matrix elements of $Q_\pm^q$ and its Fierz transform are the same. For this choice $Q_\pm^q$ have well-defined and distinct isospin quantum numbers and do not mix with each other at NLO and beyond. The definitions of the evanescent operators required to preserve the diagonal form of the NNLO anomalous dimension matrix (ADM) in the $Q_\pm^q$ basis can be found in App. A.1.

4.2 Initial Conditions

We now turn our attention to the calculation of the initial conditions of $Q_\pm^q$. Dropping the unnecessary flavor index q we write for $i = \pm$

$$C_i(\mu_W) = C_i^{(0)}(\mu_W) + \frac{\alpha_s(\mu_W)}{4\pi} C_i^{(1)}(\mu_W) + \left(\frac{\alpha_s(\mu_W)}{4\pi}\right)^2 C_i^{(2)}(\mu_W)\,, \tag{24}$$

where $\alpha_s(\mu_W)$ denotes the strong coupling constant in the $\overline{\text{MS}}$ scheme for five active quark flavors. The values of the coefficients $C_\pm^{(k)}(\mu_W)$ are determined by matching Green's functions in the full and the effective theory at μ_W. In the NNLO approximation this requires the calculation of one-particle-irreducible two-loop diagrams. Sample SM graphs are displayed in Fig. 5. For what concerns the regularization of infrared (IR) divergences we follow the procedure outlined for example in [31, 32], which consists in using dimensional regularization for both IR and ultraviolet (UV) divergences. While the former singularities are removed by renormalization, the latter poles cancel out in the difference between the full and the effective theory amplitudes. For detailed descriptions of higher-order matching calculations of strong and electroweak corrections applying the latter method we refer the interested reader to [32–34].

Using naive dimensional regularization (NDR) [35] with a fully anticommuting γ_5, we obtain for the standard choices of the Casimir invariants $C_A = 3$, $C_F = 4/3$, and five active

quark flavors

$$
\begin{aligned}
C_\pm^{(0)}(\mu_W) &= 1\,, \\
C_\pm^{(1)}(\mu_W) &= \pm\frac{1}{2}\left(1\mp\frac{1}{3}\right)\left(11+6\ln\frac{\mu_W^2}{M_W^2}\right)\,, \\
C_\pm^{(2)}(\mu_W) &= -\frac{1}{3600}\left(135677\mp 124095\right)+\frac{1}{18}\left(7\pm 51\right)\pi^2\mp\frac{1}{2}\left(1\mp\frac{1}{3}\right)T(x_t) \\
&\quad -\frac{5}{36}\left(11\mp 249\right)\ln\frac{\mu_W^2}{M_W^2}+\frac{1}{6}\left(7\pm 51\right)\ln^2\frac{\mu_W^2}{M_W^2}\,.
\end{aligned}
\tag{25}
$$

The function $T(x_t)$ depends on the top quark $\overline{\rm MS}$ mass via $x_t = m_t^2(\mu_W)/M_W^2$. It originates from SM diagrams like the one shown on the left of Fig. 5. Subtracting the corresponding terms in the gluon propagator in the momentum-space subtraction scheme at $q^2 = 0$, which ensures that $\alpha_s(\mu_W)$ is continuous at the top quark threshold μ_W,[2] we find

$$
\begin{aligned}
T(x_t) &= \frac{112}{9}+32x_t+\left(\frac{20}{3}+16x_t\right)\ln x_t \\
&\quad -\left(8+16x_t\right)\sqrt{4x_t-1}\,{\rm Cl}_2\left(2\arcsin\left(\frac{1}{2\sqrt{x_t}}\right)\right)\,,
\end{aligned}
\tag{26}
$$

where ${\rm Cl}_2(x) = {\rm Im}({\rm Li}_2(e^{ix}))$. As far as the one-loop initial conditions, namely $C_\pm^{(1)}(\mu_W)$ are concerned, our results agree with those of [27,36]. They also agree with the results obtained in [37,38] after a transformation to our renormalization scheme specified by Eqs. (A.2). The general formalism of a change of renormalization scheme discussed in detail in [39] can also be used to verify that our result for the two-loop initial conditions $C_\pm^{(2)}(\mu_W)$ coincides with the findings of [32]. This is shown in App. A.2.

4.3 Anomalous Dimensions

The Wilson coefficients are evolved from μ_W down to the relevant low-energy scale μ with the help of the RG equation. In this way, large logarithms of the form $\ln(\mu^2/\mu_W^2)$ are resummed to all orders in α_s. In mass-independent renormalization schemes like $\overline{\rm MS}$ the RG equation is given by

$$
\mu\frac{d}{d\mu}C_i(\mu) = \gamma_{ji}(\mu)C_j(\mu)\,,
\tag{27}
$$

where $\gamma_{ji}(\mu)$ is the entry of the ADM describing the mixing of Q_j into Q_i. In the case of $Q_\pm^q$ we will denote the diagonal entries of $\hat\gamma(\mu)$ by $\gamma_\pm(\mu)$.

[2] This scheme coincides with $\overline{\rm MS}$ for $\mu \le \mu_W$. For details see for example [32, 34].



Figure 6: Sample diagrams for the $\mathcal{O}(\alpha_s^3)$ mixing among the current-current operators. The fermion loop in the right Feynman graph contains f active quark flavors.

In the NNLO approximation the ADM has the following perturbative expansion

$$\hat{\gamma}(\mu) = \frac{\alpha_s(\mu)}{4\pi}\hat{\gamma}^{(0)} + \left(\frac{\alpha_s(\mu)}{4\pi}\right)^2 \hat{\gamma}^{(1)} + \left(\frac{\alpha_s(\mu)}{4\pi}\right)^3 \hat{\gamma}^{(2)}\,, \tag{28}$$

where the coefficients $\hat{\gamma}^{(k)}$ can be extracted from the one-, two-, and three-loop QCD renormalization constants in the effective theory. The renormalization matrices are found by calculating amputated Green's functions with single insertions of $Q^q_\pm$ up to three loops. Sample diagrams are shown in Fig. 6. The corresponding amplitudes are evaluated using the method that has been described in [40–42]. We keep the gauge parameter arbitrary and find it to cancel from $\hat{\gamma}^{(k)}$, which provides a powerful check of our calculation. To distinguish between IR and UV divergences, we introduce a common mass M for all fields and expand all loop integrals in inverse powers of M. This makes the calculation of the UV divergences possible at three loops, as M becomes the only relevant internal scale, and three-loop tadpole integrals with a single non-zero mass are known [41,43]. Comprehensive discussions of the technical details of the renormalization of the effective theory and the actual calculation of the operator mixing are given in [40, 42].

While $\gamma_\pm^{(0)}$ is renormalization-scheme independent, $\gamma_\pm^{(1)}$ and $\gamma_\pm^{(2)}$ are not. In the NDR scheme supplemented by the definition of evanescent operators given in Eqs. (A.2), we obtain for $C_A = 3$, $C_F = 4/3$, and an arbitrary number of active quark flavors f

$$\begin{aligned}
\gamma_\pm^{(0)} &= \pm 6\left(1 \mp \frac{1}{3}\right)\,,\\
\gamma_\pm^{(1)} &= \left(-\frac{21}{2} \pm \frac{2}{3}f\right)\left(1 \mp \frac{1}{3}\right)\,,\\
\gamma_\pm^{(2)} &= \frac{1}{300}\left(349049 \pm 201485\right) - \frac{1}{1350}\left(115577 \mp 9795\right) f\\
&\quad \mp \frac{130}{27}\left(1 \mp \frac{1}{3}\right) f^2 \mp \left(672 + 80\left(1 \mp \frac{1}{3}\right) f\right)\zeta(3)\,.
\end{aligned} \tag{29}$$

Here $\zeta(x)$ is the Riemann zeta function with the value $\zeta(3) \approx 1.20206$. Again, we find agreement with the one- and two-loop results of [27,36], and therefore also with the findings of [37,38,42] that were obtained in different renormalization schemes. We also confirm the three-loop results presented recently [39]. The explicit formulas that allow the conversion of the latter anomalous dimensions to our scheme can be found in App. A.2.

4.4 Threshold Corrections

In order to compute the Wilson coefficients for scales μ much lower than μ_W a proper matching between effective theories containing f and $f-1$ active quark flavors has to be performed each time one passes through a flavor threshold. It is achieved by requiring that the Green's functions in both effective theories are the same at the point $\mu_f = \mathcal{O}(m_f)$ where the quark with mass m_f is integrated out. This equality translates into

$$\left\langle \vec{Q}^{f-1}(\mu_f) \right\rangle^T \vec{C}^{f-1}(\mu_f) = \left\langle \vec{Q}^{f}(\mu_f) \right\rangle^T \vec{C}^{f}(\mu_f)\,, \tag{30}$$

where the labels f and $f-1$ indicate to which effective theory the variable belongs. Including corrections up to NNLO we write

$$\left\langle \vec{Q}^{f}(\mu_f) \right\rangle^T = \left\langle \vec{Q}^{f} \right\rangle^{(0)T} \left(\hat{1} + \frac{\alpha_s^f(\mu_f)}{4\pi} \hat{r}^{f(1)\,T}(\mu_f) + \left(\frac{\alpha_s^f(\mu_f)}{4\pi} \right)^2 \hat{r}^{f(2)\,T}(\mu_f) \right)\,, \tag{31}$$

where $\langle \vec{Q}^f \rangle^{(0)}$, $\hat{r}^{f(1)}(\mu_f)$, and $\hat{r}^{f(2)}(\mu_f)$ codify the tree-level, one-, and two-loop matrix element of the column vector $\vec{Q}^f$ containing the relevant physical operators. The other quantities entering Eq. (30) can be expanded in a similar fashion.

Another subtlety arises when working in mass-independent renormalization schemes, because the matching conditions connecting the strong coupling constants of the effective theories with f and $f-1$ active quark flavors are non-trivial in such schemes. In particular, in the $\overline{\text{MS}}$ scheme one has in the NNLO approximation [44, 45][3]

$$\begin{aligned} \alpha_s^{f-1}(\mu_f) = \alpha_s^f(\mu_f) \Bigg(& 1 - \frac{\alpha_s^f(\mu_f)}{4\pi} \frac{2}{3} \ln \frac{\mu_f^2}{m_f^2} \\ & + \left(\frac{\alpha_s^f(\mu_f)}{4\pi} \right)^2 \left(\frac{22}{9} - \frac{38}{3} \ln \frac{\mu_f^2}{m_f^2} + \frac{4}{9} \ln^2 \frac{\mu_f^2}{m_f^2} \right) \Bigg)\,, \end{aligned} \tag{32}$$

where $m_f = m_f(m_f)$ denotes the quark $\overline{\text{MS}}$ mass. Of course, the appearance of both logarithmic and finite corrections can be avoided by adjusting the renormalization scheme

[3] It should be noted that the non-logarithmic term in Eq. (32) differs from the result published in [44]. The authors of [44] have revised their original analysis and have found agreement with [45].



Figure 7: Examples of diagrams that contribute to the $\mathcal{O}(\alpha_s)$ matrix elements of the current-current operators.

so that $\alpha_s^{f-1}(\mu_f) = \alpha_s^f(\mu_f)$. While this does not affect the physical amplitudes [39], one leaves the class of mass-independent renormalization schemes with the drawback that the usual RG equations do not hold below the matching point and the resummation of large logarithms gets obscured. Hence it is much more convenient to stick to the $\overline{\text{MS}}$ prescription of α_s and to apply Eq. (32) whenever a flavor threshold is crossed. We will follow this approach below.

In terms of the discontinuities

$$\delta\vec{C}^{(k)}(\mu_f) = \vec{C}^{f(k)}(\mu_f) - \vec{C}^{f-1(k)}(\mu_f)\,, \qquad \delta\hat{r}^{(k)}(\mu_f) = \hat{r}^{f(k)}(\mu_f) - \hat{r}^{f-1(k)}(\mu_f)\,, \tag{33}$$

the solution of Eq. (30) can be written in a relatively compact form. Up to the second power in the strong coupling constant we obtain

$$\begin{aligned}
\delta\vec{C}^{(0)}(\mu_f) &= 0\,,\\[2ex]
\delta\vec{C}^{(1)}(\mu_f) &= -\delta\hat{r}^{(1)\,T}(\mu_f)\,\vec{C}^{f(0)}(\mu_f)\,,\\
\delta\vec{C}^{(2)}(\mu_f) &= -\left(\delta\hat{r}^{(1)\,T}(\mu_f) + \frac{2}{3}\ln\frac{\mu_f^2}{m_f^2}\right)\vec{C}^{f(1)}(\mu_f)\\
&\quad - \left(\delta\hat{r}^{(2)\,T}(\mu_f) - \hat{r}^{f-1(1)\,T}(\mu_f)\,\delta\hat{r}^{(1)\,T}(\mu_f) + \frac{2}{3}\ln\frac{\mu_f^2}{m_f^2}\,\hat{r}^{f(1)\,T}(\mu_f)\right)\vec{C}^{f(0)}(\mu_f)\,,
\end{aligned} \tag{34}$$

where the second line resembles the NLO result derived in [46]. Note that at NNLO the logarithmic $\mathcal{O}(\alpha_s^2)$ correction entering the right-hand side of Eq. (32) starts to contribute to the matching conditions of the Wilson coefficients at each flavor threshold.

In the case of $C_\pm(\mu)$ the explicit expressions for the threshold corrections turn out to be much simpler than suggested by Eqs. (34), because the corrections $\delta r_\pm^{(1)}(\mu_f)$ vanish, as the $\mathcal{O}(\alpha_s)$ matrix elements of the current-current operators are identical in the effective theories. Sample diagrams can be seen in Fig. 7. In consequence $\delta C_\pm^{(1)}(\mu_f) = 0$. Note that



Figure 8: Sample diagrams for the $\mathcal{O}(\alpha_s^2)$ matching corrections to the Wilson coefficients of the current-current operators at each flavor threshold. At these thresholds the number of active quarks changes from f to $f-1$.

this is in contrast to the case of the QCD and electroweak penguin operators which receive non-trivial threshold corrections at NLO [46, 47]. However, non-vanishing discontinuities $\delta r_\pm^{(2)}(\mu_f)$ arise from the diagrams depicted in Fig. 8. For what concerns the calculation of the graphs itself, we have adopted two different methods to regulate IR divergences and found identical results for the threshold corrections. The first approach mentioned earlier, uses dimensional regularization for both IR and UV singularities and calculates on-shell matrix elements with zero external momenta. The second method uses small quark masses as IR regulators and computes matrix elements with zero external momenta which are now off-shell. Useful details on the latter procedure can be found in [48]. The unphysical coefficients $\hat{r}^{(k)}(\mu_f)$ differ in both cases and depend on the IR regulators. However, this dependence cancels in the combination entering $\delta C_\pm^{(2)}(\mu_f)$. The correct implementation of the discontinuity in α_s of Eq. (32) and of similar decoupling relations for the gluon and quark fields are of crucial importance for this cancellation. In the second method using off-shell matrix elements another subtlety occurs, as now both sides of Eq. (30) depend on the gauge parameter, and in order to obtain a gauge-independent and IR-safe result one has to take into account that the gauge parameter is discontinous across flavor thresholds as well. We do not give the decoupling relations for the gluon, the quark field, and the gauge parameter here. They can be found for example in [45].

At the bottom quark threshold scale μ_b we find for the non-trivial matching conditions of the Wilson coefficients of the current-current operators in the NDR scheme

$$\delta C_\pm^{(2)}(\mu_b) = -\eta_b^{\pm\frac{9}{23}\left(1\mp\frac{1}{3}\right)}\left(\frac{2}{3}\ln\frac{\mu_b^2}{m_b^2}\left(\frac{631\pm 9699}{6348}(1-\eta_b)+\eta_b C_\pm^{(1)}(\mu_W)\right)\right.$$
$$\left.\mp\left(1\mp\frac{1}{3}\right)\left(\frac{59}{36}+\frac{1}{3}\ln\frac{\mu_b^2}{m_b^2}+\ln^2\frac{\mu_b^2}{m_b^2}\right)\right), \tag{35}$$

where $\eta_b = \alpha_s(\mu_W)/\alpha_s(\mu_b)$ and $m_b = m_b(m_b)$ denotes the bottom quark $\overline{\rm MS}$ mass. We also remark that diagrams like the one shown on the right of Figs. 7 and 8, which correspond to

QCD corrections to a current operator, do not contribute once all counterterms have been included. The coefficients $\delta C_\pm^{(2)}(\mu_b)$ depend on the renormalization scheme chosen for $Q_\pm^q$, in particular on the specific structure of the evanescent operator defined in the second line of Eqs. (A.2). Choices other than these would lead to operator mixing between $Q_\pm^q$.

The discontinuities $\delta C_\pm^{(2)}(\mu_c)$ at the charm quark threshold scale μ_c can be ignored as it is more convenient to express the final low-energy Wilson coefficient in terms of the α_s of the effective theory with four active quark flavors rather than in terms of the α_s of the effective theory with three active quark flavors, because no RG equation needs to be solved below μ_c. This will be explained in more detail at the end of Sec. 6.

5 Neutral and Charged Currents

5.1 Neutral Current: Z-boson Exchange

The low-energy effective Hamiltonian describing the interactions of neutrinos and quarks mediated by Z-boson exchange is given by

$$\mathcal{H}_{\text{eff}}^Z = \frac{\pi\alpha}{M_W^2 \sin^2\theta_W} C_Z(\mu) Q_Z \,, \tag{36}$$

where

$$Q_Z = \sum_q \left(\left(I_q^3 - 2e_q \sin^2\theta_W \right) Q_V^q - I_q^3 \left(Q_A^q + Q_{CS} \right) \right) , \tag{37}$$

and the sum over q extends over all active light quark flavors at the renormalization scale μ, while $I_q^3 = (+1/2, -1/2)$ and $e_q = (+2/3, -1/3)$ denote the third component of the weak-isospin and the electric charge of the up- and down-type quarks, respectively. The appropriate normalization of the electromagnetic coupling α and the weak mixing angle $\sin^2\theta_W$ will become clear after our discussion in Sec. 6.

Removing the Z-boson as an active degree of freedom from the effective theory induces a vector as well as an axial-vector coupling of the left-handed neutrino current to quarks

$$Q_V^q = \sum_{\ell=e,\mu,\tau} (\bar{q}\gamma_\mu q)(\bar{\nu}_{\ell L}\gamma^\mu \nu_{\ell L}) \,, \qquad Q_A^q = \sum_{\ell=e,\mu,\tau} (\bar{q}\gamma_\mu\gamma_5 q)(\bar{\nu}_{\ell L}\gamma^\mu \nu_{\ell L}) \,. \tag{38}$$

In the literature on $K^+ \to \pi^+\nu\bar{\nu}$ the operator Q_V^q is usually omitted,[4] as is does not contribute to the decay rate through NLO. We keep Q_V^q throughout our NNLO calculation. While individual diagrams are non-vanishing, we verify explicitly that both the two-loop matching diagrams and the three-loop mixing diagrams with Q_V^q sum to zero. We will discuss this issue in more detail in Sec. 6 after presenting our final results for the anomalous dimensions and matrix elements, respectively.

[4] To our knowledge the only exception is the recent publication [6].



Figure 9: The one-loop top quark contribution to the coupling of the Z-boson to two and three gluons. Diagrams obtained by the interchange of the external gluons are not shown.

As can be inferred from Fig. 9, decoupling the top quark generates furthermore an effective gauge-variant coupling of the left-handed neutrino current to two and three gluons which can be expressed in terms of the following Chern-Simons operator

$$Q_{CS} = \frac{g^2}{8\pi^2}\,\epsilon^{\mu_1\mu_2\mu_3\mu_4}\left(G^a_{\mu_1}\partial_{\mu_2}G^a_{\mu_3} + \frac{1}{3}gf^{abc}G^a_{\mu_1}G^b_{\mu_2}G^c_{\mu_3}\right)\sum_{\ell=e,\mu,\tau}\left(\bar{\nu}_{\ell L}\gamma_{\mu_4}\nu_{\ell L}\right). \tag{39}$$

Here g denotes the strong coupling constant, $\epsilon^{\mu_1\mu_2\mu_3\mu}$ is the fully antisymmetric Levi-Civita tensor defined with $\epsilon^{0123} = +1$, $G^a_{\mu_1}$ is the gluon field, and f^{abc} are the totally antisymmetric structure constants of $SU(3)$. We remark that the 't Hooft-Veltman (HV) prescription [49] and dimensional reduction (DRED) [50] lead to the same result for the triangle diagrams, if the mathematically consistent formulation of the DRED scheme presented recently in [51] is employed. A description of the HV scheme can be found for example in [27].

The inclusion of Q_{CS} in Eq. (37) is essential to obtain the correct anomalous Ward identity for the axial-vector current [18] and in consequence to guarantee the vanishing of the anomalous dimension of Q_Z to all orders in perturbation theory. We stress that we do not add this contribution in an ad hoc way, instead Q_{CS} is generated in an unambigous way from the diagrams in Fig. 9. Our effective theory is anomaly free, because Q_{CS} cancels the anomalous contribution from the triangle graph with a bottom quark, just as the anomalous effects from top and bottom quarks cancel in the SM. Let us illustrate how the cancellation between the contributions from Q^q_A and Q_{CS} to the anomalous dimension of Q_Z occurs at lowest order. As depicted in Fig. 10, the first non-trivial mixing arises at $\mathcal{O}(\alpha_s^2)$ with Q^q_A mixing into itself through two-loop diagrams and Q_{CS} mixing into Q^q_A through a one-loop diagram. Choosing the operator basis as (Q_Z, Q_{CS}), we find for the NLO anomalous dimension matrix[5]

$$\hat{\gamma}^{(1)} = C_F\begin{pmatrix} 0 & 0 \\ -12 & 12 \end{pmatrix}, \tag{40}$$

[5]The calculation has been performed in the background field gauge for the gluon field [52], which makes it possible maintain explicit gauge invariance at the level of off-shell Green's functions [30], keeping the gauge parameter arbitrary.

in agreement with [17]. At NNLO one needs further an evanescent operator so that $\hat{\gamma}^{(1)}$ is enlarged to a 3×3 matrix.

In the chosen operator basis the LO contributions to the initial values of the Wilson coefficients are

$$(C_Z(\mu_W), C_{CS}(\mu_W)) = (1, 0)\,. \tag{41}$$

The particular form of $\hat{\gamma}^{(1)}$ then ensures that the Wilson coefficients up to NLO satisfy $(C_Z(\mu), C_{CS}(\mu)) = (1, 0)$ at any scale μ. In fact, this scale independence is a striking consequence of the Adler-Bardeen theorem [53], which states that the Adler-Bell-Jackiw (ABJ) anomaly [18] of the axial-vector current is not renormalized in perturbation theory. This theorem is strictly proven to all orders for the abelian case [30, 53], while strong arguments suggest that it holds true for the non-abelian case [54]. Assuming that the ABJ anomaly equation survives renormalization, it is easy to show that $C_Z(\mu)$ is scale independent if and only if $C_{CS}(\mu)$ does not receive radiative corrections in the chosen operator basis, where Eq. (41) holds. In a renormalizable anomaly-free theory, such as the SM [55], this can always be achieved by invoking an additional finite renormalization of the axial-vector current [17, 30, 56]. For what concerns $C_Z(\mu)$ this means that one has to perform a finite renormalization of Q_A^q to obtain the matching condition $C_{CS}(\mu_W) = 0$ beyond one loop. The corresponding finite $\mathcal{O}(\alpha_s^2)$ correction to the renormalization constant Z_{AA} will be computed in Sec. 6. Also this finite renormalization is not an ad hoc addition to our calculation, but originates from the loop diagrams in Fig. 17 containing a top quark. Instead of absorbing these effects into Z_{AA} one could include them in $C_Z(\mu_W)$. In this case one would also find a non-zero anomalous dimension of Q_Z. Since both terms combine to reproduce the effect of Z_{AA} the physical result is however unchanged. Furthermore, owing to the definition of Q_Z in Eq. (36), the Wilson coefficient of Q_{CS} does not receive a matching correction at the bottom quark threshold scale μ_b. As the anomalous dimensions of operators in the effective theory correspond to coefficients of large logarithms in the full theory, the RG invariance of $C_Z(\mu)$ implies that anomalous subdiagrams involving the Z-boson do not give rise to logarithms $\ln(m_b^2/m_t^2)$ in the associated SM amplitudes to all orders in perturbation theory. In contrast, large logarithms proportional to m_c^2/M_W^2, which are relevant to our calculation, may arise. Such terms correspond to higher-dimensional operators, which are a priori not covered by the Adler-Bardeen theorem. In Sec. 6 we will, however, show by an explicit three-loop calculation that the latter terms are absent in the $\mathcal{O}(\alpha_s^2)$ charm quark contribution to the $s \to d\nu\bar{\nu}$ transition in the SM.

5.2 Charged Current: W-Exchange

In contrast to the neutral-current case, the discussion of the effective charged-current couplings can be kept rather short. The interactions between leptons and quarks mediated by



Figure 10: Diagrams describing the mixing of Q_A^q and Q_{CS} into Q_A^q and E_A^q at $\mathcal{O}(\alpha_s^2)$. The fermion loop containing f quark flavors is anomalous, if f is odd. The Feynman graph in which the fermion flow in the closed quark line is opposite to the one shown in the left diagram is not displayed.

W-boson exchange are encoded in the following low-energy effective Hamiltonian

$$\mathcal{H}_{\rm eff}^W = \frac{4G_F}{\sqrt{2}}\, C_W(\mu) \sum_{q=u,c} \left(V_{qs} Q_3^q + V_{qd}^* Q_4^q\right) , \tag{42}$$

where

$$Q_3^q = \sum_{\ell=e,\mu,\tau} (\bar{s}_L \gamma_\mu q_L)(\bar{\nu}_{\ell L} \gamma^\mu \ell_L) , \qquad Q_4^q = \sum_{\ell=e,\mu,\tau} (\bar{q}_L \gamma_\mu d_L)(\bar{\ell}_L \gamma^\mu \nu_{\ell L}) . \tag{43}$$

Since the effective charged-current couplings Q_3^q and Q_4^q do not mix under renormalization the Wilson coefficient $C_W(\mu)$ is μ-independent. The normalization of Eq. (42) is chosen such that $C_W(\mu) = 1$.

6 Z-Penguin Contributions

6.1 Effective Hamiltonian

After integrating out the top quark and the heavy electroweak gauge bosons we first encounter an effective Hamiltonian which is valid for scales μ in the range $\mu_c \le \mu \le \mu_W$ with dynamical bottom and charm quark fields. The Z-penguin contribution involves $\mathcal{H}_{\rm eff}^{CC}$ and $\mathcal{H}_{\rm eff}^{Z}$ defined in Eqs. (22) and (36) as well as the effective Hamiltonian

$$\mathcal{H}_{\rm eff}^{P\nu} = \frac{G_F}{\sqrt{2}} \lambda_c \frac{\pi\alpha}{M_W^2 \sin^2\theta_W} C_\nu^P(\mu) Q_\nu , \tag{44}$$

which finally brings the leading dimension-eight operator Q_ν of Eq. (21) into play.

The desired matrix element $\langle \pi^+ \nu\bar{\nu} | \mathcal{T} | K^+ \rangle$ involves the transition operator $\mathcal{T} = \mathcal{T}^P + \mathcal{T}^B$, where $\mathcal{T}^P$ and $\mathcal{T}^B$ denote the Z-penguin and electroweak box contribution, respec-



Figure 11: Examples of Z-penguin diagrams that contribute to the initial value of the Wilson coefficient of the leading dimension-eight operator Q_ν at $\mathcal{O}(\alpha_s^2)$.

tively. The Z-penguin contribution to the transition operator takes the following form

$$\begin{aligned} -\mathcal{T}^P &= \mathcal{H}_{\rm eff}^{P\nu} - i\int d^4x\, T\big(\mathcal{H}_{\rm eff}^{CC}(x)\mathcal{H}_{\rm eff}^{Z}(0)\big) \\ &= \frac{G_F}{\sqrt{2}}\lambda_c\frac{\pi\alpha}{M_W^2\sin^2\theta_W}\big(C_\nu^P(\mu)Q_\nu + 4C_+(\mu)Q_+^P + 4C_-(\mu)Q_-^P\big)\,. \end{aligned} \tag{45}$$

Notice that in passing from the first to the second line we have used $C_Z(\mu) = 1$. The last two terms in Eqs. (45) are the bilocal composite operators $Q_\pm^P$ that involve the effective current- and neutral-current couplings $Q_\pm$ and Q_Z. The former operator has already been introduced in Eq. (19). In contrast to [9] we have defined it in terms of chiral and not "$V-A$" fermion fields. This results in the factors of 4 multiplying $C_\pm(\mu)$ in the above equation.

As the normalization of α is determined by the short distance interactions at μ_W, the Wilson coefficients are appropriately expressed in terms of G_F using the relation $g^2(\mu_W)/4\pi = \alpha(\mu_W)/\sin^2\theta_W(\mu_W) = \sqrt{2}/\pi\, G_F M_W^2$, where all running couplings are defined in the $\overline{\rm MS}$ scheme. The typical case is that of electroweak box diagrams, to be discussed in the next section, which are clearly proportional to $g^4(\mu_W)/M_W^2 \propto G_F^2 M_W^2$. After decoupling, all short distance information is encoded in the Wilson coefficients and in G_F, which does not evolve in the effective theory. Hence the electromagnetic coupling α and the weak mixing angle $\sin^2\theta_W$ entering Eqs. (45) and (93) are naturally evaluated at the weak scale [22].

6.2 Initial Conditions

The matching corrections for $C_\nu^P(\mu)$ are again found by requiring equality of perturbative amplitudes generated by the full and the effective theory. Examples of two-loop Z-penguin SM diagrams can be seen in Fig. 11. Regulating spurious IR divergences dimensionally we



Figure 12: Diagrams involving the double operator insertions $(Q_\pm^q, Q_A^q)$, $(Q_\pm^q, E_A^q)$, and (Q_3^q, Q_4^q).

obtain for the non-zero matching conditions in the NDR scheme

$$\begin{aligned} C_\nu^{P(1)}(\mu_W) &= 8\left(2 + \ln\frac{\mu_W^2}{M_W^2}\right) , \\ C_\nu^{P(2)}(\mu_W) &= 4C_F\left(33 + 4\pi^2 + 34\ln\frac{\mu_W^2}{M_W^2} + 12\ln^2\frac{\mu_W^2}{M_W^2}\right) , \end{aligned} \tag{46}$$

where the first line recalls the NLO result [9], while the second one represents the new NNLO expression.

6.3 Anomalous Dimensions: Non-Anomalous Contributions

The mixing of lower- into higher-dimensional operators through double insertions leads in general to inhomogeneous RG equations [29]. In the case of the Wilson coefficient $C_\nu^P(\mu)$ introduced in Eq. (45) one has explicitly

$$\mu\frac{d}{d\mu}C_\nu^P(\mu) = \gamma_\nu(\mu)C_\nu^P(\mu) + 4\sum_{i=\pm}\gamma_{i,\nu}^P(\mu)C_i(\mu) , \tag{47}$$

where $\gamma_\nu(\mu)$ encodes the self-mixing of Q_ν, while the anomalous dimension tensor $\gamma_{\pm,\nu}^P(\mu)$ describes the mixing of the bilocal composite operators $Q_\pm^P$ into Q_ν. The factor of 4 in the above relation is of course a direct consequence of the factors of 4 in Eq. (45).

Since the conserved current $\bar{s}_L\gamma_\mu d_L$ in Q_ν is not renormalized, the RG evolution of Q_ν stems solely from the prefactor m_c^2/g^2 in Eq. (21). In terms of the expansion coefficients of the anomalous dimension of the charm quark $\overline{\rm MS}$ mass and of the QCD β-function, the corresponding anomalous dimension reads

$$\gamma_\nu^{(k)} = 2\left(\gamma_m^{(k)} - \beta_k\right) . \tag{48}$$



Figure 13: Sample diagrams for the mixing of the double insertion $(Q_\pm^q, Q_Z)$ into Q_ν at $\mathcal{O}(\alpha_s^2)$.

In the particular case of QCD one has up to the NNLO level[6]

$$\begin{aligned}
&\gamma_m^{(0)} = 8\,, \quad \gamma_m^{(1)} = \frac{404}{3} - \frac{40}{9} f\,, \quad \gamma_m^{(2)} = 2498 - \left(\frac{4432}{27} + \frac{320}{3}\zeta(3)\right) f - \frac{280}{81} f^2\,, \\
&\beta_0 = 11 - \frac{2}{3} f\,, \quad \beta_1 = 102 - \frac{38}{3} f\,, \quad \beta_2 = \frac{2857}{2} - \frac{5033}{18} f + \frac{325}{54} f^2\,.
\end{aligned} \tag{49}$$

The contributions to the anomalous dimension tensor $\gamma_{\pm,\nu}^P(\mu)$ stemming from non-anomalous diagrams can be decomposed in the following way

$$\gamma_{\pm,\nu}^{P(k)} = -\frac{1}{2}\gamma_{\pm,\nu}^{A(k)} - \left(\frac{1}{2} - \frac{2}{3}\sin^2\theta_W\right)\gamma_{\pm,\nu}^{V(k)}\,, \tag{50}$$

where the superscript A and V marks the corrections arising from diagrams with a double operator insertion $(Q_\pm^q, Q_A^q)$ and $(Q_\pm^q, Q_V^q)$. In the NDR scheme supplemented by the definition of evanescent operators given in Eqs. (A.2) we obtain after setting $C_A = 3$ and $C_F = 4/3$ the following coefficients

$$\begin{aligned}
&\gamma_{\pm,\nu}^{A(0)} = -4\,(1 \pm 3)\,, && \gamma_{\pm,\nu}^{V(0)} = 0\,, \\
&\gamma_{\pm,\nu}^{A(1)} = 16\,(2 \mp 11)\,, && \gamma_{\pm,\nu}^{V(1)} = 0\,, \\
&\gamma_{\pm,\nu}^{A(2)} = -\frac{2}{225}\,(45124 \pm 484917) + 32\,(13 \pm 15)\,\zeta(3) \pm 144 f\,, && \gamma_{\pm,\nu}^{V(2)} = 0\,.
\end{aligned} \tag{51}$$

The results in the second line agree with the findings for $\gamma_{\pm 3}^{(1)}$ of the prior NLO calculation [9] if one takes into account *i*) a factor of $-1/2$ arising from the decomposition of $\gamma_{\pm,\nu}^{P(k)}$ in Eq. (50) and *ii*) a factor of 4 that stems from the fact that our operators $Q_\pm^P$ and Q_ν are

[6] We have calculated the anomalous dimension of the quark mass and the strong coupling constant in the $\overline{\rm MS}$ scheme up to the three-loop level, finding perfect agreement with the literature [17, 57].



Figure 14: Sample diagrams for the $\mathcal{O}(\alpha_s^3)$ mixing of $(Q_\pm^q, Q_Z)$ into Q_ν.

defined in terms of chiral and not as traditionally done "$V-A$" fermion fields. The third line shows our new NNLO results. We stress that also at NNLO the part of the double operator insertion $(Q_\pm^q, Q_Z)$ proportional to $Q_\pm^c Q_A^c - Q_\pm^u Q_A^u$ accounts for the complete mixing. In order to understand this feature it is important to realize that one can distinguish two kinds of contributions: *i*) diagrams in which Q_Z couples to an up-type quark as on the left of Figs. 12, 13, and 14, and *ii*) diagrams in which Q_Z couples to a down-type quark as on the right of Figs. 13 and 14. This classification holds true to all orders in QCD. Diagrams of type *i*) containing an insertion of the vector part of Q_Z do not contribute to the anomalous dimensions. Further diagrams of type *ii*) vanish in LO and are UV-finite at NLO, but do have UV poles at NNLO. However, their overall contribution is cancelled by diagrams like the ones shown in Fig. 15, which induce a flavor off-diagonal wave function renormalization. Of course, this additional wave function renormalization has to be included in the renormalization of Q_Z. Finally let us mention that the contributions from diagrams of type *ii*) containing an insertion of the axial- and vector part of Q_Z have opposite signs, which is a consequence of $Q_\pm^q$ containing only left-handed down and strange quark fields.

6.4 Anomalous Dimensions: Anomalous Contributions

In order to calculate the $\mathcal{O}(\alpha_s^3)$ mixing of the double insertions $(Q_\pm^q, Q_Z)$ into Q_ν, we will need the renormalization constants of Q_A^q and Q_{CS} defined in Eqs. (38) and (39) up to $\mathcal{O}(\alpha_s^2)$, because these operators appear as subloop counterterms in the effective theory. Diagrams involving such subgraphs can be seen in Fig. 16. The renormalized operators Q_A^q and Q_{CS} defined in Eqs. (38) and (39) may be expressed in terms of the bare ones as

$$\begin{aligned} Q_A^q &= Z_{AA} Q_{A,0}^q + Z_{AE} E_{A,0}^q \,, \\ Q_{CS} &= \mu^{-2\epsilon}\, Q_{CS,0} + Z_{CA} Q_{A,0}^q + Z_{CE} E_{A,0}^q \,, \end{aligned} \tag{52}$$

where the unexpected factor $\mu^{-2\epsilon}$ stems from the relation between the bare and the renormalized strong coupling constant. Note first that Q_A^q is protected by its gauge invariance



Figure 15: Sample diagrams for the flavor off-diagonal wave function renormalization at $\mathcal{O}(\alpha_s^2)$.

from non-diagonal renormalization involving the gauge-variant operator Q_{CS}, and second that Q_{CS} has no diagonal renormalization due to the factor g^2 in its definition.

Within dimensional regularization the renormalization of Q_A^q is not exhausted by a multiplicative factor, but involves mixing with the following evanescent operator as well

$$E_A^q = i\,\epsilon^{\mu_1\mu_2\mu_3\mu_4}\,(\bar{q}\gamma_{\mu_1}\gamma_{\mu_2}\gamma_{\mu_3}q)\sum_{\ell=e,\mu,\tau}(\bar{\nu}_{\ell L}\gamma_{\mu_4}\nu_{\ell L}) + 6Q_A^q\,. \tag{53}$$

In our case the quark fields in Q_A^q and E_A^q correspond to an open fermion line. We will calculate the parts of the anomalous dimensions that involve anomalous subloops with insertions of Q_A^q using three different prescriptions for γ_5 for this open line, namely NDR, HV, and DRED. Together with the two possibilities to treat γ_5 in the closed fermion loop, which are HV and DRED, this amounts to six renormalization prescriptions in total. It is instructive to see how different scheme-dependent pieces combine into a scheme-independent result for $P_c(X)$. Note that diagrams with an insertion E_A^q must be included not only in the NDR and HV schemes [27–30], but also in DRED, which is unexpected at first sight. The crucial point here is that a mathematically consistent definition of DRED involves infinite-dimensional spaces just as NDR and HV: the DRED scheme entails *i*) a formally 4-dimensional, but really infinite-dimensional, space for the gauge fields and Dirac matrices, and *ii*) a formally n-dimensional space for the momenta, which is a subspace of the former one [51]. In consequence, E_A^q is not identical to zero in DRED, as it belongs to the formally $n-4$-dimensional complement of the n-dimensional space.

The renormalization constants Z_{AA}, Z_{AE}, Z_{CA}, and Z_{CE} entering Eqs. (52) are found by calculating the UV divergent parts of Feynman diagrams in the effective theory. Sample graphs encoding the first non-trivial mixing of the set (Q_A^q, Q_{CS}) into Q_A^q and E_A^q are displayed in Fig. 10. In the $\overline{\text{MS}}$ scheme we obtain

$$\begin{aligned} Z_{AA}^{(2,1)} &= 3C_F\,, & Z_{AE}^{(2,1)} &= -\frac{1}{2}C_F\,,\\ Z_{CA}^{(2,1)} &= -6C_F\,, & Z_{CE}^{(2,1)} &= C_F\,, \end{aligned} \tag{54}$$

where the symbol $Z_{ij}^{(k,l)}$ denotes the coefficient of the $1/\epsilon^l$ pole of the $\mathcal{O}(\alpha_s^k)$ term of the



Figure 16: Examples of diagrams involving the double operator insertion $(Q_\pm^q, Q_A^q)$ and $(Q_\pm^q, Q_{CS})$. In the $(Q_\pm^q, Q_A^q)$ case the fermion loop containing f quark flavors is anomalous, if f is odd.

associated renormalization constant. By taking into account the factor $\mu^{-2\epsilon}$ present in the second line of Eqs. (52) and switching to the basis (Q_Z, Q_{CS}) one recovers the ADM given in Eq. (40). All the one-, two-, and three-loop results presented in Eqs. (54), (55), (62) and (63) are again calculated using two different methods. In the first approach, IR singularities are regulated by introducing a common mass parameter into all the propagator denominators including the gluon ones [40, 41], while in the second one only the mass of the open quark line is kept non-zero [48]. The two methods give the same results for the $\overline{\text{MS}}$ renormalization constants.

The aforementioned finite renormalization of Q_A^q is most easily found by insisting that the $\mathcal{O}(\alpha_s^2)$ correction to its initial condition is identical to zero. This matching requires the calculation of the two graphs shown in Fig. 17. The UV divergences from these diagrams are canceled by a counterterm proportional to $Z_{AA}^{(2,1)}$. The leftover finite contribution can be either absorbed into the initial value of the Wilson coefficient of Q_A^q or into a finite renormalization constant $Z_{AA}^{(2,0)}$. The latter possibility is more convenient, as it avoids a spurious RG running of the effective neutral-current coupling Q_Z, which would otherwise occur beyond NLO. We find

$$Z_{AA}^{\Delta(2,0)} = \frac{3}{2} C_F \,, \tag{55}$$

for both HV and DRED. In the former scheme we reproduce the result of [17]. With the superscript Δ we indicate that we have only considered the contributions related to anomalous graphs. The contributions from all other diagrams, which have only open fermion lines, can be discussed separately. If the HV scheme is used for the latter diagrams, an additional finite renormalization constant is needed [17, 30, 56].

While we could rely on the Adler-Bardeen theorem to ensure that the contributions of Q_A^q and Q_{CS} cancel in the renormalization of Q_Z, the situation is more complicated in the case of the transition operator encountered in Eq. (45), because it involves double insertions of the type $(Q_\pm^q, Q_A^q)$ and $(Q_\pm^q, Q_{CS})$. Typical examples of such graphs are shown in Fig. 16. Apparently, their renormalization requires counterterms proportional to



Figure 17: The SM diagrams one has to compute in order to find the $\mathcal{O}(\alpha_s^2)$ correction to the initial value of the Wilson coefficient of Q_A^q.

Q_ν. The associated renormalization constants $Z^P_{\pm j,\nu}(\mu)$ can be extracted at any given order in α_s by requiring

$$\langle Q^P_{\pm j}(\mu)\rangle + Z^P_{\pm j,\,\nu}(\mu)\,\langle Q_{\nu,0}(\mu)\rangle\,, \tag{56}$$

to be UV finite. Here

$$Q^P_{\pm j} = -i\int d^4x\, T\big(Q^c_\pm(x)Q_j(0) - Q^u_\pm(x)Q_j(0)\big)\,, \tag{57}$$

and $j = A, C, E$, while $\langle \ldots \rangle$ denotes matrix elements which include the proper QCD renormalization of the coupling, the masses and the fields. Note that since $Q^q_\pm$ and Q_j are renormalized operators, all subloop divergences are properly canceled in Eq. (56). Hence the renormalization constants $Z^P_{\pm j,\nu}(\mu)$ are sufficient to achieve a finite result.

The general form of the anomalous dimension tensor for double insertions has been derived in [29]. In the following discussion we will only need the explicit expression for the part of $\gamma^P_{\pm,\,\nu}(\mu)$ related to anomalous diagrams given by

$$\gamma^\Delta_{\pm,\,\nu}(\mu) = -\sum_{k=A,C}\Big(\mu\frac{d}{d\mu}Z^\Delta_{\pm k,\,\nu}(\mu) + \Big(\sum_{i=\pm}\gamma_i(\mu)Z^\Delta_{ik,\,\nu}(\mu) + \sum_{j=A,C,E}\gamma_{kj}(\mu)Z^\Delta_{\pm j,\,\nu}(\mu)\Big)\Big)Z^{-1}_\nu(\mu)\,. \tag{58}$$

where $\gamma_i(\mu)$ and $\gamma_{kj}(\mu)$ are the elements of the ADM in the (Q^q_+, Q^q_-) and (Q^q_A, Q_{CS}, E^q_A) sector, while $Z_\nu(\mu)$ denotes the renormalization constant of Q_ν.

The renormalization constants $Z^I_{ij,\,\nu}(\mu)$ have the following perturbative expansion

$$Z^I_{ij,\,\nu}(\mu) = \sum_{k=1}^{\infty}\left(\frac{\alpha_s(\mu)}{4\pi}\right)^k Z^{I(k)}_{ij,\,\nu}\,, \qquad Z^{I(k)}_{ij,\,\nu} = \sum_{l=0}^{k}\frac{1}{\epsilon^l}Z^{I(k,l)}_{ij,\,\nu}\,, \tag{59}$$

for $I = P, \Delta$. Following the standard $\overline{\rm MS}$ prescription, $Z^I_{ij,\,\nu}(\mu)$ is given by pure $1/\epsilon^l$ poles, except when $i = \pm$ and $j = E$. In the latter case, the renormalization constant is finite

to make sure that the matrix elements of double insertions involving evanescent operators vanish in $n = 4$ dimensions [27–29].

The finite parts of Eq. (58) in the limit ϵ going to zero gives the anomalous dimension tensor. Performing an expansion in powers of the strong coupling one recognizes that the first non-trivial correction to $\gamma^{\Delta}_{\pm,\nu}(\mu)$ arises at the third order. We obtain

$$\gamma^{\Delta(2)}_{\pm,\nu} = 6Z^{\Delta(3,1)}_{\pm A,\nu} + 4Z^{P(3,1)}_{\pm C,\nu} - 4Z^{(2,1)}_{AE} Z^{P(1,0)}_{\pm E,\nu} - 2Z^{(2,1)}_{CE} Z^{P(1,0)}_{\pm E,\nu} - 4Z^{\Delta(2,0)}_{AA} Z^{P(1,1)}_{\pm A,\nu} \,, \tag{60}$$

which clearly verifies the impact of the finite renormalization of the evanescent operator E^q_A and the axial-vector coupling Q^q_A. Note that in the above equation the superscript Δ has been replaced by P whenever possible. The renormalization constants $Z^{\Delta(3,1)}_{\pm A,\nu}$ and $Z^{P(3,1)}_{\pm C,\nu}$ are found by calculating the three- and two-loop diagrams shown in Fig. 16, whereas the determination of $Z^{P(1,1)}_{\pm A,\nu}$ and $Z^{P(1,0)}_{\pm E,\nu}$ requires only a one-loop computation. The relevant Feynman graphs are displayed on the left-hand side of Fig. 12.

On the other hand the pole parts of Eq. (58) must vanish. From this condition one obtains relations between single, double and triple $1/\epsilon$ poles of the renormalization constants. In our case the non-trivial ones read

$$\begin{aligned} 6Z^{\Delta(3,2)}_{\pm A,\nu} - 4Z^{(2,1)}_{AA} Z^{P(1,1)}_{\pm A,\nu} &= 0 \,, \\ 4Z^{P(3,2)}_{\pm C,\nu} - 2Z^{(2,1)}_{CA} Z^{P(1,1)}_{\pm A,\nu} &= 0 \,. \end{aligned} \tag{61}$$

These equations constitute a powerful check of our three-loop calculation. For instance, an erroneous omission of the factor $\mu^{-2\epsilon}$ in the second line of Eqs. (52) changes Eq. (60) as well as Eqs. (61), and indeed leads to a failure of the check.

We now give the values of the renormalization constants entering Eq. (60) for the three possible renormalization prescriptions for the open fermion line. The quantities of Eqs. (54) and

$$Z^{P(1,1)}_{\pm A,\nu} = -2\,(1 \pm C_A) \,, \tag{62}$$

do not depend on the treatment of γ_5 in the open fermion line. This is not the case for the remaining ones. In the $\overline{\text{MS}}$ scheme we find

$$Z^{\Delta(3,1)}_{\pm A,\nu} = \begin{cases} -4C_F\,(3 \pm C_A) \\ -8C_F \end{cases}, \quad Z^{P(3,1)}_{\pm C,\nu} = \begin{cases} 3C_F\,(5 \pm C_A) \\ 3C_F\,(3 \mp C_A) \end{cases}, \quad Z^{P(1,0)}_{\pm E,\nu} = \begin{cases} 36\,(1 \pm C_A) \\ 0 \end{cases}, \tag{63}$$

where the expressions in the first line correspond to the NDR scheme, while the second line shows the HV and DRED results. Amazingly, HV and DRED defined as in [51] give exactly the same results for all renormalization constants through NNLO.

Inserting Eqs. (54), (55), (62), and (63) into Eq. (60), we see that $\gamma^{\Delta(2)}_{\pm,\nu}$ vanishes in all six renormalization schemes. This non-trivial result implies that anomalous subloops involving the Z-boson do not give rise to a NNLO logarithm $\ln(m_b^2/m_t^2)$ proportional to

m_c^2/M_W^2 in the decay amplitude of $K^+ \to \pi^+\nu\bar{\nu}$. We have checked the absence of these $\mathcal{O}(\alpha_s^2)$ terms explicitly by calculating the three-loop SM diagrams containing an anomalous bottom quark loop and verifying that in the limit m_b going to zero no IR divergence appear in the corresponding amplitude. Beyond NNLO the non-logarithmic pieces of three-loop diagrams containing anomalous subgraphs will be relevant and it is highly non-trivial whether the cancellation between the effects from top and bottom quark triangles carries over to this and higher orders.

6.5 RG Evolution

Since in our renormalization scheme specified by the evanescent operators in Eqs. (A.2) the Wilson coefficients $C_\pm(\mu)$ evolve independently from each other, Eq. (47) splits into two inhomogeneous differential equations. Using Eq. (27) the RG evolution of the Wilson coefficients entering the Z-penguin contribution may then be recast into the following homogeneous differential equation [9, 58]

$$\mu\frac{d}{d\mu}\vec{C}_P(\mu) = \hat{\gamma}_P^T(\mu)\vec{C}_P(\mu)\,, \tag{64}$$

where

$$\vec{C}_P(\mu) = \begin{pmatrix} 4C_+(\mu) \\ 4C_-(\mu) \\ C_\nu^P(\mu) \end{pmatrix}\,, \qquad \hat{\gamma}_P(\mu) = \begin{pmatrix} \gamma_+(\mu) & 0 & \gamma_{+,\nu}^P(\mu) \\ 0 & \gamma_-(\mu) & \gamma_{-,\nu}^P(\mu) \\ 0 & 0 & \gamma_\nu(\mu) \end{pmatrix}\,, \tag{65}$$

which can be solved by the standard techniques [36, 46, 47] introduced for single operator insertions. Since $\hat{\gamma}_P(\mu)$ and $\alpha_s(\mu)$ depend on the number of active quark flavors f, we have to solve Eq. (64) separately for $\mu_b \le \mu \le \mu_W$ and $\mu_c \le \mu \le \mu_b$. At the bottom quark threshold scale μ_b additional matching corrections, which will be discussed later in this section, have to be taken into account. The Wilson coefficients $\vec{C}_P(\mu)$ are given by

$$\vec{C}_P(\mu) = \hat{U}_P(\mu,\mu_W)\vec{C}_P(\mu_W)\,. \tag{66}$$

Keeping the first three terms in the expansions of $\hat{\gamma}_P(\mu)$ and of the QCD β-function, one finds for the evolution matrix $\hat{U}_P(\mu,\mu_W)$ in the NNLO approximation [39, 59]

$$\hat{U}_P(\mu,\mu_W) = \hat{K}_P(\mu)\hat{U}_P^{(0)}(\mu,\mu_W)\hat{K}_P^{-1}(\mu_W)\,, \tag{67}$$

where

$$\begin{aligned} \hat{K}_P(\mu) &= \hat{1} + \frac{\alpha_s(\mu)}{4\pi}\hat{J}_P^{(1)} + \left(\frac{\alpha_s(\mu)}{4\pi}\right)^2\hat{J}_P^{(2)}\,, \\ \hat{K}_P^{-1}(\mu_W) &= \hat{1} - \frac{\alpha_s(\mu_W)}{4\pi}\hat{J}_P^{(1)} - \left(\frac{\alpha_s(\mu_W)}{4\pi}\right)^2\left(\hat{J}_P^{(2)} - \left(\hat{J}_P^{(1)}\right)^2\right)\,, \end{aligned} \tag{68}$$

and

$$\hat{U}_P^{(0)}(\mu,\mu_W) = \hat{V}_P \,\mathrm{diag}\left(\frac{\alpha_s(\mu_W)}{\alpha_s(\mu)}\right)^{a_P^i} \hat{V}_P^{-1}\,, \tag{69}$$

denotes the LO evolution matrix, which is expressed through the eigenvalues a_P^i of $\hat{\gamma}_P^{(0)T}$ and the corresponding diagonalizing matrix $\hat{V}_P$:

$$\left(\hat{V}_P^{-1}\hat{\gamma}_P^{(0)T}\hat{V}_P\right)_{ij} = 2\beta_0 a_P^i \delta_{ij}\,. \tag{70}$$

In order to give the explicit expressions for the matrices $\hat{J}_P^{(1)}$ and $\hat{J}_P^{(2)}$ we define

$$\hat{J}_P^{(k)} = \hat{V}_P \hat{S}_P^{(k)} \hat{V}_P^{-1}\,, \qquad \hat{G}_P^{(k)} = \hat{V}_P^{-1}\hat{\gamma}_P^{(k)T}\hat{V}_P\,, \tag{71}$$

for $k = 1, 2$. The entries of the matrix kernels $\hat{S}_P^{(1)}$ and $\hat{S}_P^{(2)}$ are given by

$$\begin{aligned}
\left(\hat{S}_P^{(1)}\right)_{ij} &= \frac{\beta_1}{\beta_0} a_P^i \delta_{ij} - \frac{\left(\hat{G}_P^{(1)}\right)_{ij}}{2\beta_0\left(1 + a_P^i - a_P^j\right)}\,, \\
\left(\hat{S}_P^{(2)}\right)_{ij} &= \frac{\beta_2}{2\beta_0} a_P^i \delta_{ij} + \sum_k \frac{1 + a_P^i - a_P^k}{2 + a_P^i - a_P^j}\left(\left(\hat{S}_P^{(1)}\right)_{ik}\left(\hat{S}_P^{(1)}\right)_{kj} - \frac{\beta_1}{\beta_0}\left(\hat{S}_P^{(1)}\right)_{ij}\delta_{jk}\right) \\
&\quad - \frac{\left(\hat{G}_P^{(2)}\right)_{ij}}{2\beta_0\left(2 + a_P^i - a_P^j\right)}\,,
\end{aligned} \tag{72}$$

where the first line recalls the familiar NLO result [47], while the second and third represent the corresponding NNLO expression derived in [39, 59].

We will now collect the various expressions that enter the RG analysis of the Z-penguin contribution. The LO evolution from μ_W down to μ_b is described by

$$\hat{U}_P^{5\,(0)} = \begin{pmatrix} \eta_b^{\frac{6}{23}} & 0 & 0 \\ 0 & \eta_b^{-\frac{12}{23}} & 0 \\ \frac{12}{5}\left(\eta_b^{\frac{6}{23}} - \eta_b^{\frac{1}{23}}\right) & \frac{6}{13}\left(\eta_b^{-\frac{12}{23}} - \eta_b^{\frac{1}{23}}\right) & \eta_b^{\frac{1}{23}} \end{pmatrix}. \tag{73}$$

Adding an extra index for the number of flavors, the corresponding matrices $\hat{J}_P^{(k)}$ read

$$\hat{J}_P^{5\,(1)} = \begin{pmatrix} \frac{5165}{3174} & 0 & 0 \\ 0 & -\frac{2267}{1587} & 0 \\ -\frac{15857}{1587} & \frac{15305}{3174} & -\frac{14924}{1587} \end{pmatrix}, \tag{74}$$

and

$$\hat{J}_P^{5\,(2)} = \begin{pmatrix} -7.35665 & 0 & 0 \\ 0 & -54.9107 & 0 \\ 17.7699 & -1.7514 & 18.3025 \end{pmatrix}, \tag{75}$$

where in the latter matrix we have employed the numerical value of $\zeta(3)$.

The LO evolution from μ_b down to μ_c is characterized by

$$\hat{U}_P^{4\,(0)} = \begin{pmatrix} \eta_{cb}^{\frac{6}{25}} & 0 & 0 \\ 0 & \eta_{cb}^{-\frac{12}{25}} & 0 \\ \frac{12}{7}\left(\eta_{cb}^{\frac{6}{25}} - \eta_{cb}^{-\frac{1}{25}}\right) & \frac{6}{11}\left(\eta_{cb}^{-\frac{12}{25}} - \eta_{cb}^{-\frac{1}{25}}\right) & \eta_{cb}^{-\frac{1}{25}} \end{pmatrix}, \tag{76}$$

where $\eta_{cb} = \alpha_s(\mu_b)/\alpha_s(\mu_c)$. The corresponding matrices $\hat{J}_P^{(k)}$ take the following form

$$\hat{J}_P^{4\,(1)} = \begin{pmatrix} \frac{6719}{3750} & 0 & 0 \\ 0 & -\frac{3569}{1875} & 0 \\ -\frac{15931}{1875} & \frac{5427}{1250} & -\frac{15212}{1875} \end{pmatrix}, \tag{77}$$

and

$$\hat{J}_P^{4\,(2)} = \begin{pmatrix} -10.2451 & 0 & 0 \\ 0 & -50.3422 & 0 \\ 8.0325 & -0.3657 & 4.91177 \end{pmatrix}. \tag{78}$$

In the last relation terms proportional to $\zeta(3)$ have not been spelled out explicitly again. The unbracketed superscripts of the above matrices indicates whether the object belongs to the effective theory with five or four active quark flavors.

6.6 Threshold Corrections

Since $\vec{C}_P(\mu)$ contains the Wilson coefficients $C_\pm(\mu)$ it receives a non-trivial $\mathcal{O}(\alpha_s^2)$ matching correction when passing from the effective theory with five active quark flavors to the one with only four. The explicit expression for the discontinuities $\delta C_\pm^{(2)}(\mu_b)$ can be found in Eq. (35). In the case of $C_\nu^P(\mu)$ one has to distinguish two possible sources of discontinuities, corresponding to the two terms in the first line of Eqs. (45): *i*) radiative corrections to Q_ν alone and *ii*) diagrams with double operator insertions $(Q_\pm^q, Q_Z)$. In the first case only a single one- and a single two-loop diagram similar to the ones shown on the right of Figs. 7 and 8 can be drawn. These contributions are canceled by counterterms and the matrix elements are zero. Sample diagrams of the second type are displayed on the left of Fig. 12 and in Fig. 13. Since none of them contains a virtual bottom quark the discontinuities of

the corresponding matrix elements vanish identically. By matching the effective theories at the bottom quark threshold scale μ_b we obtain from Eqs. (34) in the NDR scheme

$$\begin{aligned}\delta C_\nu^{P(2)}(\mu_b) = -\frac{2}{3}\ln\frac{\mu_b^2}{m_b^2}\Bigg(&\left(\frac{284704}{2645}+\frac{694522}{20631}\eta_b\right)\eta_b^{\frac{1}{23}} - \left(\frac{1033492}{7935}+\frac{8264}{529}\eta_b\right)\eta_b^{\frac{6}{23}} \\ &+ \left(\frac{3058}{1587}+\frac{18136}{6877}\eta_b\right)\eta_b^{-\frac{12}{23}} + \eta_b\left(\eta_b^{\frac{1}{23}} C_\nu^{P(1)}(\mu_W)\right. \\ &\left. + \frac{48}{5}\left(\eta_b^{\frac{6}{23}}-\eta_b^{\frac{1}{23}}\right)C_+^{(1)}(\mu_W) + \frac{24}{13}\left(\eta_b^{-\frac{12}{23}}-\eta_b^{\frac{1}{23}}\right)C_-^{(1)}(\mu_W)\right)\Bigg),\end{aligned} \tag{79}$$

where $m_b = m_b(m_b)$ denotes the bottom quark $\overline{\text{MS}}$ mass.

6.7 Matrix Elements

For scales μ below μ_c the transition operator in the case of the Z-penguin contribution is simply given by $-\mathcal{T}^P = \mathcal{H}_{\text{eff}}^P$ with

$$\mathcal{H}_{\text{eff}}^P = \frac{4G_F}{\sqrt{2}}\frac{\alpha}{2\pi\sin^2\theta_W}\lambda_c\sum_{\ell=e,\mu,\tau} C_P(\mu)(\bar{s}_L\gamma_\mu d_L)(\bar{\nu}_{\ell L}\gamma^\mu\nu_{\ell L})\,, \tag{80}$$

which is part of the low-energy effective Hamiltonian that we have encountered already in Eq. (1). The bilocal contribution to $\mathcal{T}^P$ in Eq. (45) has disappeared, because the charm quark field is integrated out and the effect from the charm quark loop is absorbed into $C_P(\mu_c)$ through the matching calculation at μ_c. There is still a bilocal contribution from the up quark loop, but its contribution is suppressed by a factor of $\Lambda_{\text{QCD}}^2/m_c^2$ with respect to the one stemming from the charm quark. The former is not included in our formalism. This power-suppressed contribution contains genuine long-distance effects and has been computed in [6]. It will be included in our numerical analysis presented in Sec. 9.

The local operator entering Eq. (80) has zero anomalous dimension. Therefore $C_P(\mu)$ is μ-independent for scales μ below μ_c. Since we do not need to solve a RG equation for $\mu \le \mu_c$, there is no need to express the result in terms of the α_s of the effective theory containing three active quark flavors and we can avoid to include the non-trivial matching corrections of Eq. (32) at the charm quark threshold scale μ_c. In terms of the α_s of the effective theory with four active quark flavors the product $C_P(\mu_c)\langle Q_\nu(\mu_c)\rangle$ takes the following form

$$C_P(\mu_c)\langle Q_\nu\rangle^{(0)} = \frac{x_c(\mu_c)}{32}\frac{4\pi}{\alpha_s(\mu_c)}\left(C_\nu^P(\mu_c)\langle Q_\nu\rangle^{(0)} + 4\sum_{i=\pm} C_i^P(\mu_c)\left\langle Q_i^P(\mu_c)\right\rangle\right), \tag{81}$$



Figure 18: Typical diagrams contributing to the matrix elements of $Q_\pm^P$ at $\mathcal{O}(\alpha_s)$ (left) and $\mathcal{O}(\alpha_s^2)$ (right).

where we have made use of the fact that the renormalized matrix element of Q_ν does not receive radiative corrections to all orders in α_s. Notice furthermore the factor of 4 which is a result of our definition of $Q_\pm^P$ and Q_ν given in Eqs. (19) and (21).

In order to complete the evaluation of $C_P(\mu_c)$ the renormalized matrix elements of the bilocal composite operators $Q_\pm^P$ are needed. Including corrections up to NNLO, we write them in terms of the tree-level matrix element $\langle Q_\nu \rangle^{(0)}$ in the following way

$$\left\langle Q_\pm^P(\mu_c) \right\rangle = \left(\frac{\alpha_s(\mu_c)}{4\pi} r_\pm^{P(1)}(\mu_c) + \left(\frac{\alpha_s(\mu_c)}{4\pi} \right)^2 r_\pm^{P(2)}(\mu_c) \right) \langle Q_\nu \rangle^{(0)} , \tag{82}$$

where $r_\pm^{P(1)}(\mu_c)$ and $r_\pm^{P(2)}(\mu_c)$ codify the one- and two-loop corrections, respectively. Like in the case $\gamma_{\pm,\nu}^P(\mu)$ it is useful to decompose the coefficients further into

$$r_\pm^{P(k)}(\mu_c) = -\frac{1}{2} r_\pm^{A(k)}(\mu_c) - \left(\frac{1}{2} - \frac{2}{3} \sin^2 \theta_W \right) r_\pm^{V(k)}(\mu_c) , \tag{83}$$

where the superscript A and V marks the corrections arising from diagrams with a double operator insertion $(Q_\pm^q, Q_A^q)$ and $(Q_\pm^q, Q_V^q)$.

Regulating spurious IR divergences dimensionally we obtain after setting $C_A = 3$ and $C_F = 4/3$ in the NDR scheme

$$\begin{aligned} r_\pm^{A(1)}(\mu_c) &= -2\,(1 \pm 3) \left(1 - \ln \frac{\mu_c^2}{m_c^2} \right) , & r_\pm^{V(1)}(\mu_c) &= 0 , \\ r_\pm^{A(2)}(\mu_c) &= -2\,(2 \pm 9) - 8\,(4 \pm 1) \ln \frac{\mu_c^2}{m_c^2} \pm 24 \ln^2 \frac{\mu_c^2}{m_c^2} , & r_\pm^{V(2)}(\mu_c) &= 0 , \end{aligned} \tag{84}$$

where $m_c = m_c(\mu_c)$ denotes the charm quark $\overline{\text{MS}}$ mass. The first line of the above equations agrees with the known NLO results [9] if one takes the normalizations of the operators and of $r_{\pm,\nu}^{A(k)}$ in Eq. (83) into account. See the discussion after Eq. (51). The second line



Figure 19: Typical diagrams contributing to the $\mathcal{O}(\alpha_s^2)$ matrix element of $Q_\pm^P$ (left) and the $\mathcal{O}(\alpha_s)$ flavor off-diagonal wave function renormalization (right).

represents the new NNLO expressions. We emphasize that also at the NNLO level only the part of the double operator insertion $(Q_\pm^q, Q_Z)$ proportional to $Q_\pm^c Q_A^c - Q_\pm^u Q_A^u$ gives a non-zero contribution to the matrix element of $Q_\pm^P$. To understand this feature we again distinguish Feynman graphs with coupling of Q_Z to up-type quarks as in Fig. 18 from those with down-type coupling of Q_Z as on the left of Fig. 19. The former diagrams do not contribute to the matrix elements at all. In addition the latter diagrams do not arise at NLO while at NNLO they give a finite contribution. These terms are again cancelled by corrections involving a flavor off-diagonal wave function renormalization as shown on the right of Fig. 19. Finally we remark that diagrams with coupling to down-type quarks and an insertion of Q_A^q differ only by a sign from those with an insertion of Q_V^q, because $Q_\pm^q$ contains only left-handed down and strange quark fields. We recall that in the full theory electromagnetic gauge invariance requires that terms proportional to $\sin^2\theta_W$ in the $s \to d\nu\bar{\nu}$ amplitude add to zero in the limit of vanishing external momenta. The fact that the vector part of Q_Z does not contribute to $P_c(X)$ is thus nothing else but the realization of this Ward identity in the effective theory.

6.8 Final Result

Having calculated all the necessary ingredients of the RG analysis at the NNLO level, we are now in a position to present the final result for the Z-penguin contribution to $X^\ell(x_c)$ that enters the definition of $P_c(X)$ in Eqs. (2) and (114).

In the NNLO approximation the Wilson coefficient $\vec{C}_P(\mu_c)$ of Eq. (65) has the following perturbative expansion

$$\vec{C}_P(\mu_c) = \vec{C}_P^{(0)}(\mu_c) + \frac{\alpha_s(\mu_c)}{4\pi}\vec{C}_P^{(1)}(\mu_c) + \left(\frac{\alpha_s(\mu_c)}{4\pi}\right)^2 \vec{C}_P^{(2)}(\mu_c)\,, \tag{85}$$

where

$$\vec{C}_P^{(0)}(\mu_c) = \hat{U}_P^{4\,(0)}\hat{U}_P^{5\,(0)}\vec{C}_P^{(0)}(\mu_W)\,,$$

$$
\begin{aligned}
\vec{C}_P^{(1)}(\mu_c) &= \hat{J}_P^{4\,(1)}\hat{U}_P^{4\,(0)}\hat{U}_P^{5\,(0)}\vec{C}_P^{(0)}(\mu_W) \\
&\quad + \eta_{cb}\hat{U}_P^{4\,(0)}\left(\hat{J}_P^{5\,(1)} - \hat{J}_P^{4\,(1)}\right)\hat{U}_P^{5\,(0)}\vec{C}_P^{(0)}(\mu_W) \\
&\quad + \eta_b\eta_{cb}\hat{U}_P^{4\,(0)}\hat{U}_P^{5\,(0)}\left(\vec{C}_P^{(1)}(\mu_W) - \hat{J}_P^{5\,(1)}\vec{C}_P^{(0)}(\mu_W)\right), \\
\vec{C}_P^{(2)}(\mu_c) &= \hat{J}_P^{4\,(2)}\hat{U}_P^{4\,(0)}\hat{U}_P^{5\,(0)}\vec{C}_P^{(0)}(\mu_W) \\
&\quad + \eta_{cb}\hat{J}_P^{4\,(1)}\hat{U}_P^{4\,(0)}\left(\hat{J}_P^{5\,(1)} - \hat{J}_P^{4\,(1)}\right)\hat{U}_P^{5\,(0)}\vec{C}_P^{(0)}(\mu_W) \\
&\quad + \eta_b\eta_{cb}\hat{J}_P^{4\,(1)}\hat{U}_P^{4\,(0)}\hat{U}_P^{5\,(0)}\left(\vec{C}_P^{(1)}(\mu_W) - \hat{J}_P^{5\,(1)}\vec{C}_P^{(0)}(\mu_W)\right) \\
&\quad + \eta_{cb}^2\hat{U}_P^{4\,(0)}\left(\hat{J}_P^{5\,(2)} - \hat{J}_P^{4\,(2)} - \hat{J}_P^{4\,(1)}\left(\hat{J}_P^{5\,(1)} - \hat{J}_P^{4\,(1)}\right) - \delta\vec{C}_P^{(2)}(\mu_b)\right)\hat{U}_P^{5\,(0)}\vec{C}_P^{(0)}(\mu_W) \\
&\quad + \eta_b\eta_{cb}^2\hat{U}_P^{4\,(0)}\left(\hat{J}_P^{5\,(1)} - \hat{J}_P^{4\,(1)}\right)\hat{U}_P^{5\,(0)}\left(\vec{C}_P^{(1)}(\mu_W) - \hat{J}_P^{5\,(1)}\vec{C}_P^{(0)}(\mu_W)\right) \\
&\quad + \eta_b^2\eta_{cb}^2\hat{U}_P^{4\,(0)}\hat{U}_P^{5\,(0)}\left(\vec{C}_P^{(2)}(\mu_W) - \hat{J}_P^{5\,(1)}\vec{C}_P^{(1)}(\mu_W) - \left(\hat{J}_P^{5\,(2)} - \left(\hat{J}_P^{5\,(1)}\right)^2\right)\vec{C}_P^{(0)}(\mu_W)\right).
\end{aligned}
\tag{86}
$$

The explicit expressions for $\vec{C}_P^{(k)}(\mu_W)$, $\hat{U}_P^{f\,(0)}$, $\hat{J}_P^{f\,(k)}$, and $\delta\vec{C}_P^{(2)}(\mu_b)$ have been given in Eqs. (73) to (79). We also recall that $\eta_b = \alpha_s(\mu_W)/\alpha_s(\mu_b)$ and $\eta_{cb} = \alpha_s(\mu_b)/\alpha_s(\mu_c)$.

It is useful to express the running charm quark $\overline{\rm MS}$ mass $m_c(\mu)$ entering the definition of the dimension-eight operator Q_ν of Eq. (21) in terms of the input parameter $m_c(m_c)$. At the scale μ_c the required NNLO relation reads

$$
x_c(\mu_c) = \kappa_c\left(1 + \frac{\alpha_s(\mu_c)}{4\pi}\xi_c^{(1)} + \left(\frac{\alpha_s(\mu_c)}{4\pi}\right)^2\xi_c^{(2)}\right)x_c(m_c)\,. \tag{87}
$$

Here $\kappa_c = \eta_c^{24/25}$ with $\eta_c = \alpha_s(\mu_c)/\alpha_s(m_c)$ and

$$
\begin{aligned}
\xi_c^{(1)} &= \frac{15212}{1875}\left(1 - \eta_c^{-1}\right), \\
\xi_c^{(2)} &= \frac{966966391}{10546875} - \frac{231404944}{3515625}\eta_c^{-1} - \frac{272751559}{10546875}\eta_c^{-2} - \frac{128}{5}\left(1 - \eta_c^{-2}\right)\zeta(3)\,.
\end{aligned}
\tag{88}
$$

Including corrections up to third order in perturbation theory one finds from Eq. (81):

$$
C_P(\mu_c) = \kappa_c\,\frac{x_c(m_c)}{32}\left(\frac{4\pi}{\alpha_s(\mu_c)}C_P^{(0)}(\mu_c) + C_P^{(1)}(\mu_c) + \frac{\alpha_s(\mu_c)}{4\pi}C_P^{(2)}(\mu_c)\right), \tag{89}
$$

where

$$
C_P^{(0)}(\mu_c) = C_\nu^{P(0)}(\mu_c)\,,
$$

$$
C_P^{(1)}(\mu_c) = C_\nu^{P(1)}(\mu_c) + 4\sum_{i=\pm}C_i^{P(0)}(\mu_c)\,\rho_i^{P(1)}(\mu_c) + \xi_c^{(1)}\,C_\nu^{P(0)}(\mu_c)\,,
$$

$$C_P^{(2)}(\mu_c) = C_\nu^{P(2)}(\mu_c) + 4\sum_{i=\pm}\Big(C_i^{P(1)}(\mu_c)\,\rho_i^{P(1)}(\mu_c) + C_i^{P(0)}(\mu_c)\,\rho_i^{P(2)}(\mu_c)\Big)$$
$$+\,\xi_c^{(1)}\bigg(C_\nu^{P(1)}(\mu_c) + 4\sum_{i=\pm} C_i^{P(0)}(\mu_c)\,\rho_i^{P(1)}(\mu_c)\bigg) + \xi_c^{(2)}\,C_\nu^{P(0)}(\mu_c)\,. \tag{90}$$

The factors of 4 are again a result of the definition of $Q_\pm^P$ and Q_ν in Eqs. (19) and (21).

The coefficients $\rho_\pm^{P(k)}(\mu_c)$ are obtained from $r_\pm^{P(k)}(\mu_c)$ by expanding the charm quark $\overline{\rm MS}$ mass $m_c(\mu_c)$ entering Eqs. (84) in α_s around $m_c(m_c)$. Explicitly one finds

$$\begin{aligned}
\rho_\pm^{P(1)}(\mu_c) &= r_\pm^{P(1)}(\mu_c, m_c) + (1\pm 3)\ln\kappa_c\,,\\
\rho_\pm^{P(2)}(\mu_c) &= r_\pm^{P(2)}(\mu_c, m_c) - 4(4\pm 1)\ln\kappa_c \mp 12\ln^2\kappa_c \pm 24\ln\kappa_c\ln\frac{\mu_c^2}{m_c^2} + (1\pm 3)\,\xi_c^{(1)}\,.
\end{aligned} \tag{91}$$

Here the additional argument in $r_\pm^{P(k)}(\mu_c, m_c)$ indicates that the expansion coefficients of Eqs. (83) have to be evaluated at $m_c(m_c)$ and not at $m_c(\mu_c)$. Note that the second term in the first line of the above equations is absent in the analytic NLO formulas of $P_c(X)$ presented in [9, 10]. The relevance of this μ_c-dependent term will be discussed in Sec. 9.

7 Electroweak Box Contributions

7.1 Effective Hamiltonian

Apart from the presence of a non-trivial matching correction at the bottom quark threshold scale μ_b the NNLO correction in the electroweak box sector does not involve new conceptual features compared to the LO and NLO. This simplifies the following discussion notably.

For scales μ in the range $\mu_c \le \mu \le \mu_W$ the electroweak box contribution involves $\mathcal{H}_{\rm eff}^W$ defined in Eq. (42) as well as the effective Hamiltonian given by

$$\mathcal{H}_{\rm eff}^{B\nu} = \frac{G_F}{\sqrt{2}}\lambda_c\frac{2\pi\alpha}{M_W^2\sin^2\theta_W}C_\nu^B(\mu)Q_\nu\,. \tag{92}$$

In terms of these building blocks the part of the transition operator $\mathcal{T}$ stemming from electroweak boxes can be written as

$$\begin{aligned}
-\mathcal{T}^B &= \mathcal{H}_{\rm eff}^{B\nu} - i\int d^4x\, T\big(\mathcal{H}_{\rm eff}^W(x)\mathcal{H}_{\rm eff}^W(0)\big)\\
&= \frac{G_F}{\sqrt{2}}\lambda_c\frac{2\pi\alpha}{M_W^2\sin^2\theta_W}\big(C_\nu^B(\mu)Q_\nu + 4Q^B\big)\,.
\end{aligned} \tag{93}$$

Notice that in passing from the first to the second line we used the fact that the Wilson coefficients of the effective charged-current couplings Q_3^q and Q_4^q equal one at all scales. In



Figure 20: Examples of electroweak box diagrams that contribute to the $\mathcal{O}(\alpha_s^2)$ correction to the initial value of the Wilson coefficient of the leading dimension-eight operator Q_ν.

particular they do not receive matching corrections at any scale. The last term in Eqs. (93) is the bilocal composite operators Q^B which has been introduced in Eq. (20) already. The factor of 4 originates once again from the use of chiral fermion fields in Q^B and Q_ν.

7.2 Initial Conditions

The initial conditions of $C_\nu^B(\mu)$ are as usual found by matching perturbative amplitudes in the full and the effective theory. Examples of two-loop electroweak box diagrams can be seen in Fig. 20. Regulating spurious IR divergences once dimensionally and once with small quark masses we found identical results for the initial conditions. In the NDR scheme supplemented by the definition of the evanescent operator given in Eq. (A.3), the non-zero matching conditions read

$$\begin{aligned} C_\nu^{B(1)}(\mu_W) &= -4\left(9 + 4\ln\frac{\mu_W^2}{M_W^2}\right), \\ C_\nu^{B(2)}(\mu_W) &= -8C_F\left(20 + 2\pi^2 + 25\ln\frac{\mu_W^2}{M_W^2} + 6\ln^2\frac{\mu_W^2}{M_W^2}\right), \end{aligned} \tag{94}$$

where the first line agrees with the literature [9,10], while the second one is the new NNLO expression.[7]

7.3 Anomalous Dimensions

In the case of the Wilson coefficient $C_\nu^B(\mu)$ the RG equation takes the following form

$$\mu\frac{d}{d\mu}C_\nu^B(\mu) = \gamma_\nu(\mu)C_\nu^B(\mu) + 4\gamma_\nu^B(\mu), \tag{95}$$

[7]We remark that the logarithmic term in the second line of Eqs. (94) differs from the expression one would expect from the results published in [9]. The disagreement is due to a subtlety in regulating spurious IR divergences [10, 13]. This mistake has been corrected in [10].



Figure 21: Typical examples of diagrams that describe the mixing of the double insertion (Q_3^q, Q_4^q) into the leading dimension-eight operators Q_ν at $\mathcal{O}(\alpha_s^2)$ (left) and $\mathcal{O}(\alpha_s^3)$ (right).

with $\gamma_\nu(\mu)$ given in Eq. (48). The anomalous dimension tensor $\gamma_\nu^B(\mu)$ encodes the mixing of the bilocal composite structures Q^B into Q_ν. Sample diagrams are shown in Fig. 21. The UV pole parts of these Feynman graphs are evaluated using the method that has been described earlier. The factor of 4 in the above equation is a direct result of the factor of 4 in Eq. (93).

In the NDR scheme supplemented by the definition of the evanescent operator given in Eq. (A.3) the expansion coefficients of $\gamma_\nu^B(\mu)$ read

$$\begin{aligned}
\gamma_\nu^{B(0)} &= -8 \\
\gamma_\nu^{B(1)} &= 8\,C_F\,, \\
\gamma_\nu^{B(2)} &= 2\,C_F\left(\frac{69}{C_A} - \frac{458}{3}C_A - \left(\frac{48}{C_A} - 96\,C_A\right)\zeta(3) + \frac{38}{3}f\right)\,,
\end{aligned} \tag{96}$$

where the second line differs from the findings for $\gamma_{12}^{(1)}$ of the original NLO calculation [9] even after taking into account a factor of 4 stemming from the different normalization of Q^B and Q_ν used here and therein. It however agrees with the results of [10] where the error made in [9] has been corrected. The third line represents our new NNLO result.

7.4 RG Evolution

Obviously the RG evolution of the electroweak box contribution may be recast into the following homogeneous differential equation

$$\mu\frac{d}{d\mu}\vec{C}_B(\mu) = \hat{\gamma}_B^T(\mu)\vec{C}_B(\mu)\,, \tag{97}$$

where

$$\vec{C}_B(\mu) = \begin{pmatrix} 4 \\ C_\nu^B(\mu) \end{pmatrix}\,, \qquad \hat{\gamma}_B(\mu) = \begin{pmatrix} 0 & \gamma_\nu^B(\mu) \\ 0 & \gamma_\nu(\mu) \end{pmatrix}\,. \tag{98}$$

As both $\hat{\gamma}_B(\mu)$ and $\alpha_s(\mu)$ depend on the number of active quark flavors f, we have to solve Eq. (97) separately for $\mu_b \leq \mu \leq \mu_W$ and $\mu_c \leq \mu \leq \mu_b$. At the bottom quark threshold scale μ_b additional matching corrections, which will be discussed in the next subsection, have to be taken into account.

In the following we will detail the different expressions that enter the RG analysis of the electroweak box contribution. Our notation derives from Eqs. (67) to (72) thereby. The LO evolution from μ_W down to μ_b is related to

$$\hat{U}_B^{5\,(0)} = \begin{pmatrix} 1 & 0 \\ 12\left(1-\eta_b^{\frac{1}{23}}\right) & \eta_b^{\frac{1}{23}} \end{pmatrix} . \tag{99}$$

The corresponding matrices $\hat{J}_B^{(k)}$ are given by

$$\hat{J}_B^{5\,(1)} = \begin{pmatrix} 0 & 0 \\ \frac{2402}{1587} & -\frac{14924}{1587} \end{pmatrix} , \tag{100}$$

and

$$\hat{J}_B^{5\,(2)} = \begin{pmatrix} 0 & 0 \\ \frac{1296371522}{39457581} - \frac{34624}{1081}\zeta(3) & -\frac{177621017}{7555707} + \frac{800}{23}\zeta(3) \end{pmatrix} . \tag{101}$$

The LO evolution from μ_b down to μ_c is induced by

$$\hat{U}_B^{4\,(0)} = \begin{pmatrix} 1 & 0 \\ -12\left(1-\eta_{cb}^{-\frac{1}{25}}\right) & \eta_{cb}^{-\frac{1}{25}} \end{pmatrix} . \tag{102}$$

The corresponding matrices $\hat{J}_B^{(k)}$ read

$$\hat{J}_B^{4\,(1)} = \begin{pmatrix} 0 & 0 \\ \frac{581}{1875} & -\frac{15212}{1875} \end{pmatrix} , \tag{103}$$

and

$$\hat{J}_B^{4\,(2)} = \begin{pmatrix} 0 & 0 \\ \frac{684990354}{19140625} - \frac{6976}{245}\zeta(3) & -\frac{272751559}{10546875} + \frac{128}{5}\zeta(3) \end{pmatrix} . \tag{104}$$

7.5 Threshold Corrections

In analogy to the case of $C_\nu^P(\mu)$ all discontinuities of the matrix elements that could potentially contribute to the threshold correction of $C_\nu^B(\mu)$ vanish identically. By matching the effective theories at the bottom quark threshold scale μ_b we obtain from Eqs. (34) in the



Figure 22: Typical examples of diagrams that contribute to the matrix elements of Q^B at $\mathcal{O}(\alpha_s)$ (left diagram) and $\mathcal{O}(\alpha_s^2)$ (right diagram).

NDR scheme supplemented by the definition of the evanescent operator given in Eq. (A.3) the following non-trivial correction

$$\delta C_\nu^{B(2)}(\mu_b) = -\frac{2}{3}\ln\frac{\mu_b^2}{m_b^2}\left(\left(\frac{238784}{529}-\frac{9608}{1587}\eta_b\right)\eta_b^{\frac{1}{23}}-\frac{1336}{3}+\eta_b^{\frac{24}{23}}C_\nu^{B(1)}(\mu_W)\right), \qquad (105)$$

where $m_b = m_b(m_b)$ is the bottom quark $\overline{\rm MS}$ mass.

7.6 Matrix Elements

For scales μ below μ_c the transition operator in the case of the electroweak box contributions takes the form $-\mathcal{T}^B = \mathcal{H}_{\rm eff}^B$ with

$$\mathcal{H}_{\rm eff}^B = \frac{4G_F}{\sqrt{2}}\frac{\alpha}{2\pi\sin^2\theta_W}\lambda_c\sum_{\ell=e,\mu,\tau}C_B^\ell(\mu)(\bar{s}_L\gamma_\mu d_L)(\bar{\nu}_{\ell L}\gamma^\mu\nu_{\ell L}), \qquad (106)$$

which is part of the low-energy effective Hamiltonian of Eq. (1). Again the bilocal contribution to $\mathcal{T}^B$ in Eq. (93) has disappeared, because the charm quark field is integrated out and the effect from its loop is absorbed into $C_B^\ell(\mu_c)$. The leftover contribution from the up quark loop to $\mathcal{T}^B$ is like in $\mathcal{T}^P$ power-suppressed. The numerical size of these corrections has been calculated in [6] and is included in our numerical analysis of Sec. 9.

It is again favorable to express the final low-energy Wilson coefficient in terms of the α_s of the effective theory with four active quark flavors rather than in terms of the α_s of the effective theory with three active quark flavors. Proceeding in this way the product $C_B^\ell(\mu_c)\langle Q_\nu(\mu_c)\rangle$ can be written in the form

$$C_B^\ell(\mu_c)\langle Q_\nu\rangle^{(0)} = \frac{x_c(\mu_c)}{16}\frac{4\pi}{\alpha_s(\mu_c)}\left(C_\nu^B(\mu_c)\langle Q_\nu\rangle^{(0)}+4\left\langle Q_\ell^B(\mu_c)\right\rangle\right), \qquad (107)$$

where Q_ℓ^B denotes the part of Q^B that contains a lepton of flavor ℓ. The factor of 4 is again a consequence of the definition of Q^B and Q_ν in Eqs. (20) and (21).

The renormalized matrix elements $\left\langle Q_\ell^B(\mu_c)\right\rangle$ are found by computing the finite parts of one- and two-loop diagrams. Examples can be seen in Fig. 22. Regulating spurious IR divergences once dimensionally and once with small quark masses we found identical results for the matrix elements. In the NDR scheme supplemented by the definition of the evanescent operator given in Eq. (A.3) the expansion coefficients for the tau lepton contribution to the matrix element take the following form

$$\begin{aligned} r_\tau^{B(1)}(\mu_c) &= 5 + \frac{4\,x_\tau}{1-x_\tau}\ln x_\tau + 4\ln\frac{\mu_c^2}{m_c^2}\,, \\ r_\tau^{B(2)}(\mu_c) &= -2C_F\left(\frac{9+7\,x_\tau}{1-x_\tau} + \frac{x_\tau\,(3+13\,x_\tau)}{(1-x_\tau)^2} - \frac{12\,x_\tau}{1-x_\tau}\,\mathrm{Li}_2\,(1-x_\tau)\right. \\ &\quad \left. - \left(\frac{1-13\,x_\tau}{1-x_\tau} - \frac{12\,x_\tau^2}{(1-x_\tau)^2}\ln x_\tau\right)\ln\frac{\mu_c^2}{m_c^2} - 6\ln^2\frac{\mu_c^2}{m_c^2}\right)\,. \end{aligned} \tag{108}$$

Here $x_\tau = m_\tau^2/m_c^2$ with $m_c = m_c(\mu_c)$ denotes the ratio of the tau lepton and the charm quark $\overline{\rm MS}$ mass squared. The first line of the above equations agrees with the known NLO result [9], after including the aforementioned factor of 4, while the second one represents the new NNLO expression.

In the case of the electron and the muon the lepton mass can be neglected compared to the charm quark mass. In the limit x_τ going to zero Eqs. (108) simplify to

$$\begin{aligned} r_{e,\mu}^{B(1)}(\mu_c) &= 5 + 4\ln\frac{\mu_c^2}{m_c^2}\,, \\ r_{e,\mu}^{B(2)}(\mu_c) &= -2C_F\left(9 - \ln\frac{\mu_c^2}{m_c^2} - 6\ln^2\frac{\mu_c^2}{m_c^2}\right)\,. \end{aligned} \tag{109}$$

7.7 Final Result

The analytic expression for the electroweak box contribution to $X^\ell(x_c)$ that enters the definition of $P_c(X)$ in Eq. (2) can be obtained in a straightforward manner following the detailed exposition presented at the end of Sec. 6.

In particular the perturbative expansion of the Wilson coefficient $\vec{C}_B(\mu_c)$ in Eq. (98) is given by Eqs. (85) and (86) after replacing all subscripts P by B. The explicit expressions for $\vec{C}_B^{(k)}(\mu_W)$, $\hat{U}_B^{f\,(0)}$, $\hat{J}_B^{f\,(k)}$, and $\delta\vec{C}_B^{(2)}(\mu_b)$ can be found in Eqs. (99) to (105).

Keeping terms up to third order in the strong coupling expansion Eq. (107) can be written as

$$C_B^\ell(\mu_c) = \kappa_c\,\frac{x_c(m_c)}{16}\left(\frac{4\pi}{\alpha_s(\mu_c)}C_B^{\ell(0)}(\mu_c) + C_B^{\ell(1)}(\mu_c) + \frac{\alpha_s(\mu_c)}{4\pi}C_B^{\ell(2)}(\mu_c)\right)\,, \tag{110}$$

where κ_c is defined after Eq. (87) and

$$\begin{aligned}
C_B^{\ell(0)}(\mu_c) &= C_\nu^{B(0)}(\mu_c)\,,\\
C_B^{\ell(1)}(\mu_c) &= C_\nu^{B(1)}(\mu_c) + 4\,\rho_\ell^{B(1)}(\mu_c) + \xi_c^{(1)}\,C_\nu^{B(0)}(\mu_c)\,,\\
C_B^{\ell(2)}(\mu_c) &= C_\nu^{B(2)}(\mu_c) + 4\,\rho_\ell^{B(2)}(\mu_c) + \xi_c^{(1)}\,C_\nu^{B(1)}(\mu_c) + \xi_c^{(2)}\,C_\nu^{B(0)}(\mu_c)\,.
\end{aligned} \tag{111}$$

Here the factors of 4 arise again from the use of chiral fermion fields in Q^B and Q_ν of Eqs. (20) and (21).

The coefficients $\rho_\ell^{B(k)}(\mu_c)$ are obtained from $r_\ell^{B(k)}(\mu_c)$ by expanding the charm quark $\overline{\rm MS}$ mass $m_c(\mu_c)$ entering Eqs. (108) and (109) in α_s around $m_c(m_c)$. Explicitly we find in the case of the tau lepton

$$\begin{aligned}
\rho_\tau^{B(1)}(\mu_c) &= r_\tau^{B(1)}(\mu_c, m_c) + \frac{4}{x_\tau-\kappa_c}\left(\kappa_c\ln\kappa_c - \frac{x_\tau\,(1-\kappa_c)}{1-x_\tau}\ln x_\tau\right)\,,\\
\rho_\tau^{B(2)}(\mu_c) &= r_\tau^{B(2)}(\mu_c, m_c) + \frac{32}{(x_\tau-\kappa_c)}\left(\frac{4x_\tau\,(1-\kappa_c)}{3\,(1-x_\tau)}\right.\\
&\quad -\frac{x_\tau\,(x_\tau\,(13-29\,x_\tau)+\kappa_c\,(3+29x_\tau^2)-\kappa_c^2\,(3+13x_\tau))}{12\,(x_\tau-\kappa_c)\,(1-x_\tau)^2}\ln x_\tau\\
&\quad +\frac{\kappa_c\,(17x_\tau-\kappa_c)}{12\,(x_\tau-\kappa_c)}\ln\kappa_c + \frac{x_\tau^2}{x_\tau-\kappa_c}\ln x_\tau\ln\kappa_c - \frac{x_\tau^2+2\,x_\tau\kappa_c-\kappa_c^2}{2\,(x_\tau-\kappa_c)}\ln^2\kappa_c\\
&\quad \left.-\frac{x_\tau\,(x_\tau-\kappa_c)}{2\,(1-x_\tau)}\mathrm{Li}_2\,(1-x_\tau) - x_\tau\,\mathrm{Li}_2\left(1-\frac{x_\tau}{\kappa_c}\right)\right)\\
&\quad +\frac{32}{(x_\tau-\kappa_c)\,(1-x_\tau)}\left(x_\tau\,(1-\kappa_c) + \frac{\kappa_c\,(1-x_\tau)\,(2x_\tau-\kappa_c)}{x_\tau-\kappa_c}\ln x_\tau\right.\\
&\quad \left.+\frac{x_\tau^2\,(1-\kappa_c)\,(1-2\,x_\tau+\kappa_c)}{(x_\tau-\kappa_c)\,(1-x_\tau)}\ln\kappa_c\right)\ln\frac{\mu_c^2}{m_c^2}\\
&\quad +\frac{4\,\kappa_c}{x_\tau-\kappa_c}\left(1-\frac{x_\tau}{x_\tau-\kappa_c}\ln x_\tau + \frac{x_\tau}{x_\tau-\kappa_c}\ln\kappa_c\right)\xi_c^{(1)}\,.
\end{aligned} \tag{112}$$

In the limit x_τ going to zero which is the relevant one in the case of the electron and the muon one arrives at

$$\begin{aligned}
\rho_{e,\mu}^{B(1)}(\mu_c) &= r_{e,\mu}^{B(1)}(\mu_c, m_c) - 4\ln\kappa_c\,,\\
\rho_{e,\mu}^{B(2)}(\mu_c) &= r_{e,\mu}^{B(2)}(\mu_c, m_c) - \frac{8}{3}\ln\kappa_c + 16\ln^2\kappa_c - 32\ln\kappa_c\ln\frac{\mu_c^2}{m_c^2} - 4\xi_c^{(1)}\,.
\end{aligned} \tag{113}$$

The additional argument in $r_\ell^{B(k)}(\mu_c, m_c)$ signals that the expansion coefficients of Eqs. (108) and (109) have to be evaluated at $m_c(m_c)$ and not at $m_c(\mu_c)$. The same applies

to the variables x_τ and m_c appearing explicitly in Eqs. (112) and (113). We remark that the second terms in the first lines of the latter equations are not present in the NLO formulas of $P_c(X)$ given in [9, 10]. The importance of this μ_c-dependent terms will be discussed in Sec. 9.

8 Final Result for $P_c(X)$ at NNLO

The function $X^\ell(x_c)$ that enters the definition of $P_c(X)$ in Eq. (2) is given in terms of the contribution of the Z-penguin and the electroweak boxes by

$$X^\ell(x_c) = C_P(\mu_c) + C_B^\ell(\mu_c)\,, \tag{114}$$

where the analytic NNLO expression for $C_P(\mu_c)$ and $C_B^\ell(\mu_c)$ can be found in Eqs. (89) and (110), respectively. The latter equations together with Eqs. (2) and (114) then enable one to find the analytic formula for $P_c(X)$ through $\mathcal{O}(\alpha_s)$.

The explicit analytic expression for $P_c(X)$ including the complete NNLO corrections is so complicated and long that we derive an approximate formula. Setting $\lambda = 0.2248$, $m_t(m_t) = 163.0\,\text{GeV}$ and $\mu_W = 80.0\,\text{GeV}$ we derive an approximate formula for $P_c(X)$ that summarizes the dominant parametric and theoretical uncertainties due to $m_c(m_c)$, $\alpha_s(M_Z)$, μ_c, and μ_b. It reads

$$P_c(X) = 0.3832 \left(\frac{m_c(m_c)}{1.30\,\text{GeV}}\right)^{1.3750} \left(\frac{\alpha_s(M_Z)}{0.1187}\right)^{1.9480} \left(1 + \sum_{i,j,k,l} \kappa_{ijlm} L_{m_c}^i L_{\alpha_s}^j L_{\mu_c}^k L_{\mu_b}^l\right), \tag{115}$$

where

$$\begin{aligned} L_{m_c} &= \ln\left(\frac{m_c(m_c)}{1.30\,\text{GeV}}\right), & L_{\alpha_s} &= \ln\left(\frac{\alpha_s(M_Z)}{0.1187}\right), \\ L_{\mu_c} &= \ln\left(\frac{\mu_c}{1.5\,\text{GeV}}\right), & L_{\mu_b} &= \ln\left(\frac{\mu_b}{5.0\,\text{GeV}}\right), \end{aligned} \tag{116}$$

and the sum includes the expansion coefficients κ_{ijkl} given in Tab. 3. The above formula approximates the exact NNLO result with an accuracy of $\pm 0.6\%$ in the ranges $1.15\,\text{GeV} \le m_c(m_c) \le 1.45\,\text{GeV}$, $0.1150 \le \alpha_s(M_Z) \le 0.1230$, $1.0\,\text{GeV} \le \mu_c \le 3.0\,\text{GeV}$, and $2.5\,\text{GeV} \le \mu_b \le 10.0\,\text{GeV}$. The uncertainties due to $m_t(m_t)$, μ_W, and the different methods of computing $\alpha_s(\mu_c)$ from $\alpha_s(M_Z)$, which are not quantified above, are all below $\pm 0.2\%$. Their actual size at NLO and NNLO will be discussed in the next section.

$\kappa_{1000} = 0.7432$	$\kappa_{0100} = -3.3790$	$\kappa_{0010} = -0.0001$
$\kappa_{0001} = 0.0028$	$\kappa_{1100} = -0.4350$	$\kappa_{1010} = 0.1669$
$\kappa_{0020} = -0.0903$	$\kappa_{0020} = -0.0065$	$\kappa_{0030} = 0.0330$

Table 3: The coefficients κ_{ijkl} arising in the approximate formula for $P_c(X)$ at NNLO.

9 Numerical Analysis

9.1 Theoretical Uncertainties of $P_c(X)$ at NLO

Before presenting the numerical analysis of the NNLO correction to $P_c(X)$, it is instructive to display the theoretical uncertainties present at the NLO level. These originate in the leftover unphysical dependence on μ_c but are also due to the dependence on μ_b and μ_W, and to higher order terms that arise in the evaluation of $\alpha_s(\mu_c)$ from the experimental input $\alpha_s(M_Z)$. The latter uncertainties have not been scrutinized in previous NLO analyses of the charm quark contribution [9, 10].

The dependence of $P_c(X)$ on μ_c can be seen in Fig. 23. The solid red line in the upper plot shows the NLO result obtained by evaluating $\alpha_s(\mu_c)$ from $\alpha_s(M_Z)$ solving the RG equation of α_s numerically, while the long- green and short-dashed blue lines are obtained by first determining the scale parameter $\Lambda_{\overline{\rm MS}}$ from $\alpha_s(M_Z)$, either using the explicit solution of the RG equation of α_s or by solving the RG equation of α_s iteratively for $\Lambda_{\overline{\rm MS}}$, and subsequently calculating $\alpha_s(\mu_c)$ from $\Lambda_{\overline{\rm MS}}$. The corresponding two-loop values for $\alpha_s(\mu_c)$ have been obtained with the program `RunDec` [60]. Obviously, the difference between the three curves is due to higher order terms and has to be regarded as part of the theoretical error. With its size of ± 0.012 it is comparable to the variation of the NLO result due to μ_c, amounting to ± 0.020.

In [9, 10] values for the latter uncertainty have been quoted that are more than twice as large. The observed difference is related to the definition of the charm quark mass. While in the latter publications the value $m_c(m_c)$ has been employed in the logarithms $\ln(\mu_c^2/m_c^2)$ of the one-loop matrix elements, we consistently apply $m_c(\mu_c)$ throughout our NLO analysis.

Using the $\overline{\rm MS}$ scheme and integrating out the charm quark field at the scale μ_c, the mass $m_c(\mu_c)$ appears in all intermediate steps of the computation. In particular, the bare one-loop matrix elements computed at NLO are proportional to $m_c^{2-2\epsilon}(\mu_c)$. After multiplying this with the $1/\epsilon$ poles and finite parts of the loop integrals, adding the counterterm diagrams and expanding in ϵ one finds the results given in the first lines of Eqs. (84), (108), and (109). Switching by hand to $m_c(m_c)$ in the argument of the logarithms $\ln(\mu_c^2/m_c^2)$ as done in [9], amounts thus to treating the factors of $m_c^2(\mu_c)$ and $m_c^{-2\epsilon}(\mu_c)$ differently,

Parameter	Value ± Error	Reference
$m_c(m_c)$ [GeV]	1.30 ± 0.05	[61], our average
$\alpha_s(M_Z)$	0.1187 ± 0.0020	[24]
$\mathrm{Im}\lambda_t$ $[10^{-4}]$	$1.407^{+0.096}_{-0.098}$	[19]
$\mathrm{Re}\lambda_t$ $[10^{-4}]$	$-3.13^{+0.20}_{-0.17}$	[19]
$\mathrm{Re}\lambda_c$	$-0.22006^{+0.00093}_{-0.00091}$	[19]

Table 4: Input parameters used in the numerical analysis of $P_c(X)$, $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$, $|V_{td}|$, $\sin 2\beta$, and γ.

although they stem from the very same analytical term in $n = 4 - 2\epsilon$ dimensions. It is important to realize that such a replacement *i*) introduces a correction which has no diagrammatic counterpart at two loops, and *ii*) implies a mass counterterm at NNLO which is not $\overline{\rm MS}$, as it contains an explicit $\ln(\mu_c^2/m_c^2)$ term. Using $m_c(m_c)$ in the $\ln(\mu_c^2/m_c^2)$ terms of the one-loop matrix elements is for these reasons disputable, although it leads to results that differ from the one obtained with $m_c(\mu_c)$ by terms that are formally of NNLO. These $\mathcal{O}(\alpha_s)$ terms lead to an artificially large μ_c-dependence at NLO and are hence not a good estimate of the size of the uncalculated higher order terms: substituting all factors $m_c(\mu_c)$ entering the one-loop matrix elements in a consistent way by $m_c(m_c)$ results in an uncertainty from μ_c which is close to the one quoted above. In practice this replacement is achieved by employing $m_c(m_c)$ in the logarithms $\ln(\mu_c^2/m_c^2)$ of Eqs. (84), (108), and (109), and by rescaling the NLO terms stemming from the second terms in Eqs. (81) and (107) by a factor κ_c^{-1}. Of course our conclusion is also based on the actual NNLO calculation, which indeed finds a correction that is much smaller than the theoretical uncertainty at NLO reported in [9, 10].

Finally, while in [9, 10] only μ_c was varied, the theoretical error given in Eq. (3) includes also the dependence on μ_b and μ_W of ± 0.001 each. The specified scale uncertainties correspond to the ranges $1.0\,\mathrm{GeV} \le \mu_c \le 3.0\,\mathrm{GeV}$, $2.5\,\mathrm{GeV} \le \mu_b \le 10.0\,\mathrm{GeV}$, and $40.0\,\mathrm{GeV} \le \mu_W \le 160.0\,\mathrm{GeV}$, and the quoted theoretical error has been obtained by varying them independently.

9.2 Branching Ratio for $K^+ \to \pi^+\nu\bar{\nu}$ at NLO

Using the input parameters listed in Tab. 4, we find from Eqs. (3), (6), (7), and (12) at the NLO level

$$\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu}) = \left(7.96 \pm 0.76_{P_c(X)} \pm 0.84_{\rm other}\right) \times 10^{-11}\,, \tag{117}$$



Figure 23: $P_c(X)$ as a function of μ_c at NLO (upper plot) and NNLO (lower plot). The three different lines correspond to three different methods of computing $\alpha_s(\mu_c)$ from $\alpha_s(M_Z)$ (see text).

where the second error collects the uncertainties due to κ_+, $\delta P_{c,u}$, $X(x_t)$, and the CKM elements. Numerically, the enhancement of $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ coming from $\delta P_{c,u}$ [6] has been compensated by the suppression due to the decrease of M_t [21].

9.3 Branching Ratio for $K_L \to \pi^0\nu\bar{\nu}$ at NLO

Employing the value and errors of $\mathrm{Im}\lambda_t$ as given in Tab. 4, we obtain from Eqs. (12), (17), and (18) in the NLO approximation

$$\mathcal{B}(K_L \to \pi^0\nu\bar{\nu}) = (2.85 \pm 0.05_{\mu_t} \pm 0.39_{\text{other}}) \times 10^{-11}\,, \tag{118}$$

where the second error collects the uncertainties due to κ_L, $m_t(m_t)$, and the CKM elements.

9.4 Theoretical Uncertainties of $P_c(X)$ at NNLO

Having described the details of our calculation in the previous sections, we now present our results for $P_c(X)$. From Eqs. (89), (110), and (114) we find at NNLO

$$P_c(X) = 0.375 \pm 0.009_{\text{theory}} \pm 0.031_{m_c} \pm 0.009_{\alpha_s}\,. \tag{119}$$

Obviously the error on the charm quark contribution to $K^+ \to \pi^+\nu\bar{\nu}$ is now fully dominated by the uncertainty in $m_c(m_c)$. Comparing these numbers with Eq. (3) we observe that our NNLO calculation reduces the theoretical uncertainty by a factor of 4.

As can be nicely seen in Tab. 1 and in the lower plot of Fig. 23, $P_c(X)$ depends very weakly on μ_c at NNLO, varying by only ± 0.006. Furthermore, the three different treatments of α_s affect the NNLO result by as little as ± 0.001. The three-loop values of $\alpha_s(\mu_c)$ used in the numerical analysis have been obtained with the program `RunDec` [60]. The theoretical error quoted in Eq. (119) includes also the dependence on μ_b and μ_W of ± 0.001 each. The presented scale uncertainties correspond to the ranges given earlier, and the specified theoretical error has again been obtained by varying them independently.

9.5 Branching Ratio for $K^+ \to \pi^+\nu\bar{\nu}$ at NNLO

Using Eqs. (6), (7), (12), and (119) the result in Eq. (117) is modified to the NNLO value

$$\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu}) = \left(8.01 \pm 0.49_{P_c(X)} \pm 0.84_{\text{other}}\right) \times 10^{-11}\,. \tag{120}$$

As the value of $m_c(m_c)$ is, besides the CKM parameters, the main leftover parametric uncertainty in the evaluation of $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$, we show in the upper plot of Fig. 3, $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ as a function of $m_c(m_c)$. At present the errors from the CKM parameters veils the benefit of the NNLO calculation of $P_c(X)$ presented in this paper. For completeness in the lower plot of the same figure we also show the dependence on M_t, which is significantly smaller, because M_t is much better known than $m_c(m_c)$.

Observable	Central ± 68% CL	95% CL	99% CL
$\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$ $[10^{-11}]$	$2.77^{+0.58}_{-0.49}$	$[1.80, 3.82]$	$[1.62, 4.23]$
$P_c(X)$	$0.367^{+0.050}_{-0.049}$	$[0.306, 0.427]$	$[0.293, 0.439]$
$\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ $[10^{-11}]$	$7.95^{+1.81}_{-1.67}$	$[5.61, 10.50]$	$[5.28, 11.18]$
$\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$ $[10^{-11}]$	2.56 ± 0.30	$[2.02, 3.16]$	$[1.88, 3.38]$
$P_c(X)$	0.375 ± 0.024	$[0.333, 0.418]$	$[0.324, 0.429]$
$\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ $[10^{-11}]$	7.68 ± 0.58	$[6.61, 8.87]$	$[6.32, 9.26]$

Table 5: SM predictions for $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$, $P_c(X)$, and $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ at the 68%, 95%, and 99% CL obtained by the CKMfitter Group (upper half) and the **UT***fit* Collaboration (lower half) incorporating all constraints on the CKM elements following from a global analysis of the standard UT.

9.6 Statistical Analyses of the Branching Ratios of $K \to \pi\nu\bar{\nu}$

The partial uncertainties given in Eqs. (118) and (120) are not statistically distributed. A very important issue in determining the central SM values and errors of $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$ and $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ is thus the treatment of the experimental and especially the theoretical uncertainties entering these observables. The increasing accuracy in the global analysis of the standard UT and the achieved reduction of the theoretical uncertainty of $P_c(X)$ clearly calls for a closer look at the matter in question.

To this end it is of interest to see what results are obtained by the two most developed statistical methods, namely the *R*fit approach used by the CKMfitter Group and the Bayesian approach employed by the **UT***fit* Collaboration and to identify those experimental and theoretical uncertainties for which a reduction of errors would contribute the most to the quality of the determination of the $K \to \pi\nu\bar{\nu}$ branching ratios. In this context we would like to caution the reader that a direct comparison of the results obtained by the two groups in Tab. 5 is quite challenging and the comments given below are hopefully of help for the reader to make her or his unbiased judgment of the situation. Our final result is given subsequently in Sec. 9.7.

The numerical results for $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$, $P_c(X)$, and $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ obtained by the CKMfitter Group and the **UT***fit* Collaboration are summarized in Tab. 5. The corresponding likelihood and probability density functions are displayed in Figs. 24 and 25. Apart from the CKM elements the employed input agrees with the one that has been used to obtain the numerical values for $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$, $P_c(X)$, and $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ presented earlier in Eqs. (118), (119) and (120).

While the CKMfitter Group and the **UT***fit* Collaboration find comparable errors at 95% and higher confidence levels (CL), the **UT***fit* Collaboration obtains significantly smaller



Figure 24: Likelihood of $\mathcal{B}(K_L \to \pi^0 \nu\bar{\nu})$, $P_c(X)$, and $\mathcal{B}(K^+ \to \pi^+ \nu\bar{\nu})$ following from a global CKM analysis performed by the CKMfitter Group. The borders of the 68% (95%) probability regions are indicated by the long (short) dashed lines.



Figure 25: Probability density functions of $\mathcal{B}(K_L \to \pi^0 \nu\bar{\nu})$, $P_c(X)$ and $\mathcal{B}(K^+ \to \pi^+ \nu\bar{\nu})$ following from a global CKM analysis performed by the **UT***fit* Collaboration. Dark (light) areas correspond to the 68% (95%) probability regions.

errors at the 68% CL. This difference is expected, because both groups treat theoretical errors differently: the **UT***fit* Collaboration assigns a probabilistic meaning to them while the CKMfitter Group scans for a best fit value. It can be most easily understood by discussing the value of $P_c(X)$ at NNLO. Here the dominant error is the parametric uncertainty in $m_c(m_c)$, which is treated as a theoretical uncertainty by both groups. By assigning a flat probability density for $m_c(m_c)$ within the error range of $1.25\,\text{GeV} \leq m_c(m_c) \leq 1.35\,\text{GeV}$ only 68% of this measure is used by the **UT***fit* Collaboration to compute $P_c(X)$ at the 68% CL. In consequence the error of $P_c(X)$ found by the **UT***fit* Collaboration is smaller by a factor of 0.68 compared to the error one would obtain by treating the uncertainty in $m_c(m_c)$ as the 1σ range of a Gaussian distribution. On the other hand the CKMfitter Group uses the whole parameter range of $m_c(m_c)$ to compute the error on $P_c(X)$ independently of the CL. For a flat probability density the measure is proportional to the CL such that at the 95% CL nearly the whole range of $m_c(m_c)$ is used by the **UT***fit* Collaboration. Correspondingly the difference in the results for the errors of the CKMfitter Group and the **UT***fit* Collaboration decreases strongly at the 95% and higher CL.

A detailed analysis of the individual sources of uncertainty entering the SM prediction of $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$ and $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ using a modified version of the CKMfitter package leads to the following picture. In both cases residual scale uncertainties are no longer a dominant source of error as they numerically amount to around 9% and 11% of the total error only. Hence other intrinsic theoretical errors come to fore. In the case of $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$ the error associated with r_{K_L} is now the main source of theoretical uncertainty since the error of these isospin breaking corrections of $\pm 3\%$ translates into around 15% of the total uncertainty. In the case of $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ the uncertainties associated with the parameters $\delta P_{c,u}$ and r_{K^+} become prominent. Numerically the total error introduced by the long-distance and isospin breaking corrections amounts to about 28% of the final uncertainty in $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$. This error is thus slightly larger than the error due to the charm quark mass which for $m_c(m_c) = (1.30 \pm 0.05)\,\text{GeV}$ amounts to roughly 20% of the final uncertainty. The remaining errors of about 76% and 41% for $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$ and $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$, respectively, are due to the uncertainty in the top quark mass, $\alpha_s(M_Z)$, and the CKM elements. The given numbers have been obtained by removing the individual errors from the fit in the order the have been mentioned in the text. This study makes clear that if one wants to achieve predictions of $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$ and $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ at the level of $\pm 5\%$ or below further theoretical improvements concerning the isospin breaking corrections, long-distance effects, and the determination of the charm quark mass are indispensable.

9.7 Final Predictions for $K_L \to \pi^0\nu\bar{\nu}$ and $K^+ \to \pi^+\nu\bar{\nu}$

Given the sizeable difference of the 68% CL error intervals obtained by the CKMfitter Group and the **UT***fit* Collaboration we base our final predictions on our own analysis of the charm quark contribution and the branching ratios. To determine our final results for

$\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$, $P_c(X)$, and $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ we could in principle add the errors given in Eqs. (118), (119), and (120) linearly. These estimates might be too conservative. On the other hand adding the errors in quadrature would be probably too optimistic since the uncertainties are not statistically distributed. Therefore we quote as the final result the mean of the values obtained by adding the individual errors once linearly and once in quadrature. In the case of $K_L \to \pi^0\nu\bar{\nu}$ this gives

$$\mathcal{B}(K_L \to \pi^0\nu\bar{\nu}) = (2.8 \pm 0.4) \times 10^{-11}\,, \tag{121}$$

while in the case of $K^+ \to \pi^+\nu\bar{\nu}$ one has

$$P_c(X) = 0.38 \pm 0.04\,, \tag{122}$$

and

$$\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu}) = (8.0 \pm 1.1) \times 10^{-11}\,. \tag{123}$$

The given uncertainties represent the ranges in which we believe that the true values of $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$, $P_c(X)$, and $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ are located with high probability.

9.8 Impact on the Determination of the CKM Parameters

As seen in Eq. (4) the accuracy of the determination of $|V_{td}|$, $\sin 2\beta$, and of the angle γ in the UT depends sensitively on the error in $P_c(X)$.

The reduction of the theoretical error in $P_c(X)$ from $\pm 9.8\%$ down to $\pm 2.4\%$ translates into the following uncertainties

$$\begin{aligned}
\frac{\sigma\left(|V_{td}|\right)}{|V_{td}|} &= \begin{cases} \pm 4.0\%\,, & \text{NLO}\,, \\ \pm 1.0\%\,, & \text{NNLO}\,, \end{cases} \\
\sigma\left(\sin 2\beta\right) &= \begin{cases} \pm 0.024\,, & \text{NLO}\,, \\ \pm 0.006\,, & \text{NNLO}\,, \end{cases} \\
\sigma\left(\gamma\right) &= \begin{cases} \pm 4.7^\circ\,, & \text{NLO}\,, \\ \pm 1.2^\circ\,, & \text{NNLO}\,, \end{cases}
\end{aligned} \tag{124}$$

implying a very significant improvement of the NNLO over the NLO results. In obtaining these numbers we have used $\sin 2\beta = 0.724$ and $\gamma = 58.6^\circ$ [19], and included only the theoretical errors quoted in Eqs. (3) and (119).

A comparison of $\sin 2\beta$ determined from clean B-physics observables with $\sin 2\beta$ inferred from the $K \to \pi\nu\bar{\nu}$ system offers a precise and highly non-trivial test of the CKM picture. Both determinations suffer from small theoretical errors and any discrepancy between them would signal non-CKM physics. The impact of future accurate measurements of



Figure 26: Standard UT from future measurements of $\mathcal{B}(K_L \to \pi^0 \nu\bar{\nu})$ and $\mathcal{B}(K^+ \to \pi^+ \nu\bar{\nu})$ with an accuracy of $\pm 10\%$. Dark (light) areas correspond to the 68% (95%) probability regions. In the upper (lower) panel the 68% and 95% domains following from the $K \to \pi\nu\bar{\nu}$ constraint (present global CKM fit) as found by the **UT***fit* Collaboration are overlaid. The lower plot also shows for comparison the present constraint coming from ϵ_K.



Figure 27: Constraints in the $\bar{\rho}$–$\bar{\eta}$ plane arising from future measurements of $\mathcal{B}(K_L \to \pi^0 \nu\bar{\nu})$ and $\mathcal{B}(K^+ \to \pi^+ \nu\bar{\nu})$ with an accuracy of $\pm 10\%$. The upper (lower) panel shows the likelihood obtained assuming no (optimistic) improvement of both the theoretical and experimental errors of the input parameters. For comparison the 68% probability region following from the present global CKM analysis of the CKMfitter Group is also displayed.

$K^+ \to \pi^+\nu\bar{\nu}$ and $K_L \to \pi^0\nu\bar{\nu}$ leading to $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu}) = (8.0 \pm 0.8) \times 10^{-11}$ and $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu}) = (3.0 \pm 0.3) \times 10^{-11}$ is illustrated in Figs. 27 and 26. As can be seen in Fig. 26 the expected precision of the determination of $(\bar{\rho}, \bar{\eta})$ from the $K \to \pi\nu\bar{\nu}$ system cannot quite compete with the one from the present global CKM fit performed by the **UT***fit* Collaboration. On the other hand assuming a reduction of the errors in M_t, $m_c(m_c)$, r_{K^+}, r_{K_L}, and $\delta P_{c,u}$ by a factor of 3 would put the $K \to \pi\nu\bar{\nu}$ system and the global CKM fit almost on the same level. The great potential of the $K \to \pi\nu\bar{\nu}$ system is clearly visible in the lower panel in Fig. 27 which shows the constraint in the $\bar{\rho}$–$\bar{\eta}$ plane obtained by the CKMfitter Group adopting this futuristic scenario.

Obviously, the future of the determination of the standard UT from the $K \to \pi\nu\bar{\nu}$ system will depend on the uncertainties in the measured branching ratios, on the value of $m_c(m_c)$ and also on $|V_{cb}|$. Further theoretical improvement concerning the isospin breaking and long-distance corrections would be desirable in this respect too. A corresponding numerical analysis can be found in the updated version of [3], where the NNLO correction to $P_c(X)$ presented here, will be soon included.

While the determination of $|V_{td}|$, $\sin 2\beta$, and γ from the $K \to \pi\nu\bar{\nu}$ system is without doubt of interest, with the slow progress in measuring the relevant branching ratios and much faster progress in the determination of the angle γ from $B_s \to DK$ system to be expected at LHC, the role of the $K \to \pi\nu\bar{\nu}$ system will shift towards the search for new physics rather than the determination of the CKM parameters.

Indeed, determining the CKM parameters from tree diagrams dominated K- and B-decays and thus independently of new physics contributions will allow to find the "true" values of the CKM parameters and the so-called reference unitarity triangle [62]. Inserting these, hopefully accurate, values in the formulas for the branching ratios presented here, will allow to obtain very precise preditions for the SM rates of both decays. A comparison with future data on these decays will then give a clear signal of potential new physics contributions in a theoretical clean enviroment. Even deviations by 20% from the SM expectations could be considered as signals of new physics, whereas it is not possible in most other decays in which the theoretical uncertainties are at least 10%.

10 Summary

In this paper we have calculated the complete NNLO QCD correction of the charm quark contribution to the branching ratio for the rare decay $K^+ \to \pi^+\nu\bar{\nu}$ in the SM. As the charm quark contribution is essentially unaffected by new physics, our results are also valid in basically all extensions of the SM.

The main result of our paper is summarized in the approximate but very accurate analytic expression for the relevant parameter $P_c(X)$ as a function of $m_c(m_c)$ and $\alpha_s(M_Z)$ presented in Eq. (14). The remaining scale uncertainties and the uncertainty due to higher

order terms in the computation of $\alpha_s(\mu_c)$ from $\alpha_s(M_Z)$, that is sizeable at the NLO level as seen in Fig. 23, have been drastically reduced through our calculation to a level that they can basically be ignored for all practical purposes. This can be seen in Tab. 1 and Fig. 23. Nevertheless, an approximate formula for $P_c(X)$ containing the dominant parametric and theoretical errors due to $m_c(m_c)$, $\alpha_s(M_Z)$, μ_c, and μ_b has been given in Eq. (115), which should be useful for future phenomenological analysis of the rare decay $K^+ \to \pi^+\nu\bar{\nu}$.

The values of $P_c(X)$ for different $m_c(m_c)$ and $\alpha_s(M_Z)$ are collected in Tab. 2. As $\alpha_s(M_Z)$ is already known with an accuracy of better than $\pm 2\%$, the main uncertainty in the evaluation of $P_c(X)$ resides in the value of $m_c(m_c)$. Our nominal value for $P_c(X) = 0.38 \pm 0.04$ used in the NNLO prediction for the branching ratio of $K^+ \to \pi^+\nu\bar{\nu}$ in Eq. (123) corresponds to $m_c(m_c) = (1.30 \pm 0.05)\,\text{GeV}$ but the master formulas for $P_c(X)$ in Eqs. (14) and (115) as well as Tab. 2 allow one to calculate $P_c(X)$ and $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ for other values of $m_c(m_c)$.

With the improved recent evaluation [6] of the long-distance contributions to the charm component, that can be further improved by lattice calculations [7], and hopefully an increased accuracy on $m_c(m_c)$ and r_{K^+} in the future, the theoretical computation of the relevant decay rate will reach an exceptional degree of precision, subject mainly to the uncertainties in the values of the CKM parameters. As the latter errors will be reduced to a large extend in the coming years through the B-decay experiments a prediction for $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ with an accuracy significantly below $\pm 10\%$ will be possible before the end of this decade. Such a precision is unique in the field of FCNC processes.

On the other hand, accurate measurements of $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$, in particular in conjunction with $\mathcal{B}(K_L \to \pi^0\nu\bar{\nu})$, will provide a very important extraction of the CKM parameters that compared with the information from B-decays will offer a truly unique test of the CKM mechanism both in the SM and some of its extensions. The drastic reduction of the theoretical uncertainty in $P_c(X)$ achieved by the computation presented in this paper will play an important role in these efforts and increases the power of the $K \to \pi\nu\bar{\nu}$ system in the search for new physics, in particular if $\mathcal{B}(K^+ \to \pi^+\nu\bar{\nu})$ will not differ much from the SM prediction.

Acknowledgments

We would like to thank Matthias Steinhauser for providing us with an updated version of `MATAD` [63] and A. Höcker, J. Ocariz, and M. Pierini for useful communications concerning the global analysis of the UT. Discussions with G. Buchalla, S. Jäger, H. Lacker, A. Poschenrieder, F. Schwab, L. Silvestrini, D. Stöckinger, S. Uhlig, and A. Weiler are acknowledged. Finally we are grateful to the CKMfitter Group and the **UT***fit* Collaboration for supplying the numbers and plots shown in Secs. 9.6 and 9.8. This work has been supported in part by the Bundesministerium für Bildung and Forschung under contract 05HT4WOA/3 and the Schweizer Nationalfonds. U. H. and U. N. have been supported by

the DOE under contract DE-AC02-76CH03000.

Appendix

A.1 Evanescent Operators

The evanescent operators that arise as counterterms for the one-, two- and three-loop diagrams with insertions of the current-current operators

$$\begin{aligned} Q_1^q &= (\bar{s}_L\gamma_\mu T^a q_L)\,(\bar{q}_L\gamma^\mu T^a d_L)\;, \\ Q_2^q &= (\bar{s}_L\gamma_\mu q_L)\,(\bar{q}_L\gamma^\mu d_L)\;, \end{aligned} \tag{A.1}$$

can be chosen to be

$$\begin{aligned} E_1^q &= (\bar{s}_L\gamma_{\mu_1\mu_2\mu_3}T^a q_L)(\bar{q}_L\gamma^{\mu_1\mu_2\mu_3}T^a d_L) - \left(16-4\epsilon-4\epsilon^2\right)Q_1^q\,, \\ E_2^q &= (\bar{s}_L\gamma_{\mu_1\mu_2\mu_3} q_L)(\bar{q}_L\gamma^{\mu_1\mu_2\mu_3} d_L) - \left(16-4\epsilon-4\epsilon^2\right)Q_2^q\,, \\ E_3^q &= (\bar{s}_L\gamma_{\mu_1\mu_2\mu_3\mu_4\mu_5}T^a q_L)(\bar{q}_L\gamma^{\mu_1\mu_2\mu_3\mu_4\mu_5}T^a d_L) - \left(256-224\epsilon-\frac{5712}{25}\epsilon^2\right)Q_1^q\,, \\ E_4^q &= (\bar{s}_L\gamma_{\mu_1\mu_2\mu_3\mu_4\mu_5} q_L)(\bar{q}_L\gamma^{\mu_1\mu_2\mu_3\mu_4\mu_5} d_L) - \left(256-224\epsilon-\frac{10032}{25}\epsilon^2\right)Q_2^q\,, \\ E_5^q &= (\bar{s}_L\gamma_{\mu_1\mu_2\mu_3\mu_4\mu_5\mu_6\mu_7}T^a q_L)(\bar{q}_L\gamma^{\mu_1\mu_2\mu_3\mu_4\mu_5\mu_6\mu_7}T^a d_L) - (4096-7680\epsilon)\,Q_1^q \\ E_6^q &= (\bar{s}_L\gamma_{\mu_1\mu_2\mu_3\mu_4\mu_5\mu_6\mu_7} q_L)(\bar{q}_L\gamma^{\mu_1\mu_2\mu_3\mu_4\mu_5\mu_6\mu_7} d_L) - (4096-7680\epsilon)\,Q_2^q\,. \end{aligned} \tag{A.2}$$

Here the shorthand notation $\gamma_{\mu_1\cdots\mu_m} = \gamma_{\mu_1}\cdots\gamma_{\mu_m}$ and $\gamma^{\mu_1\cdots\mu_m} = \gamma^{\mu_1}\cdots\gamma^{\mu_m}$ has been used. The above operators have been defined such that *i*) the ADM of the operators $Q_\pm^q$ introduced in Eq. (23) is diagonal through NNLO, and that *ii*) their particular structure differs only by multiples of ϵ^2 times physical operators from the evanescent operators of the "traditional" basis [27, 36]. The latter operators can be found by the procedure outlined in [64]. Up to three loops they have been given in [39]. Of course, the above choice is not unique in the sense, that there are many schemes that would satisfy *i*) through NNLO. It is however not possible to define the set of evanescent operators to be invariant under the interchange of color structures and to achieve *i*) simultaneously. Finally, we remark that the ϵ^2 terms of the above one-loop evanescent operators E_1^q and E_2^q are unambiguously determined by condition *i*).

In the case of the electroweak box contribution only one evanescent operator arises as a counterterm for the one-, two-, and three-loop diagrams considered in this paper. Following [9, 10, 13] we chose it as

$$E_\nu = \frac{m_c^2}{g^2\mu^{2\epsilon}}\sum_{\ell=e,\mu,\tau}(\bar{s}_L\gamma_{\mu_1\mu_2\mu_3}d_L)(\bar{\nu}_{\ell_L}\gamma^{\mu_1\mu_2\mu_3}\nu_{\ell_L}) - (16-4\epsilon)\,Q_\nu\,. \tag{A.3}$$

Here m_c is the charm quark $\overline{\rm MS}$ mass $m_c(\mu)$ and the explicit factors g^{-2} and $\mu^{-2\epsilon}$ follow from the normalization of Q_ν in Eq. (21).

A.2 Change from the "Standard" Basis of Current-Current Operators

Beyond LO the anomalous dimensions and the Wilson coefficients depend on the definition of the operators in $n = 4 - 2\epsilon$ dimensions. So far all of the direct NNLO calculations have been performed in the operator basis introduced in [38], which we will call "standard" basis from now on. It consists of the following set of physical and evanescent operators

$$\vec{Q}'^{\,T} = (Q_1'^q, Q_2'^q)\,, \qquad \vec{E}'^{\,T} = (E_1'^q, E_2'^q, E_3'^q, E_4'^q)\,, \tag{A.4}$$

where

$$\begin{aligned}
Q_1'^q &= (\bar{s}_L\gamma_\mu T^a q_L)\,(\bar{q}_L\gamma^\mu T^a d_L)\;,\\
Q_2'^q &= (\bar{s}_L\gamma_\mu q_L)\,(\bar{q}_L\gamma^\mu d_L)\;,\\
E_1'^q &= (\bar{s}_L\gamma_{\mu_1\mu_2\mu_3} T^a q_L)(\bar{q}_L\gamma^{\mu_1\mu_2\mu_3} T^a d_L) - 16Q_1'^q\\
E_2'^q &= (\bar{s}_L\gamma_{\mu_1\mu_2\mu_3} q_L)(\bar{q}_L\gamma^{\mu_1\mu_2\mu_3} d_L) - 16Q_2'^q\,,\\
E_3'^q &= (\bar{s}_L\gamma_{\mu_1\mu_2\mu_3\mu_4\mu_5} T^a q_L)(\bar{q}_L\gamma^{\mu_1\mu_2\mu_3\mu_4\mu_5} T^a d_L) - 256Q_1'^q - 20E_1'^q\,,\\
E_4'^q &= (\bar{s}_L\gamma_{\mu_1\mu_2\mu_3\mu_4\mu_5} q_L)(\bar{q}_L\gamma^{\mu_1\mu_2\mu_3\mu_4\mu_5} d_L) - 256Q_2'^q - 20E_2'^q\,,
\end{aligned} \tag{A.5}$$

while

$$\vec{Q}^T = (Q_+^q, Q_-^q)\,, \qquad \vec{E}^T = (E_1^q, E_2^q, E_3^q, E_4^q)\,, \tag{A.6}$$

denotes the physical and evanescent operators used in this paper. The operators E_5^q and E_6^q and their primed counterparts have been omitted in the above equations, because they do not affect the change of scheme up to the order considered here.

In this appendix we demonstrate how the results for the two-loop initial conditions [32] and the three-loop ADM [39] of the current-current operators can be transformed to our basis. This will serve as a cross-check of our results for $C_\pm^{(k)}(\mu_W)$ and $\gamma_\pm^{(k)}$ as given in Eqs. (25) and (29). In all formulas presented below we set $C_A = 3$ and $C_F = 4/3$, while the number of active quark flavors f is kept arbitrary.

The transformations relating the primed with the unprimed sets take the simple form

$$\vec{Q} = \hat{R}\vec{Q}'\,, \qquad \vec{E} = \hat{M}\left(\vec{E}' + \epsilon\,\hat{U}\vec{Q}' + \epsilon^2\,\hat{V}\vec{Q}'\right)\,, \tag{A.7}$$

where the matrix $\hat{R}$ ($\hat{M}$) describes a rotation of the physical (evanescent) operators, while the matrix $\hat{U}$ ($\hat{V}$) parameterizes a change of basis that consists of adding multiples of ϵ

(ϵ^2) times physical operators to the evanescent ones. The matrices introduced in Eq. (A.7) are given by

$$\hat{R} = \begin{pmatrix} 1 & \frac{2}{3} \\ -1 & \frac{1}{3} \end{pmatrix}, \qquad \hat{M} = \begin{pmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 20 & 0 & 1 & 0 \\ 0 & 20 & 0 & 1 \end{pmatrix},$$
$$\hat{U} = \begin{pmatrix} 4 & 0 \\ 0 & 4 \\ 144 & 0 \\ 0 & 144 \end{pmatrix}, \qquad \hat{V} = \begin{pmatrix} 4 & 0 \\ 0 & 4 \\ \frac{3712}{25} & 0 \\ 0 & \frac{8032}{75} \end{pmatrix}. \tag{A.8}$$

The change of basis in Eq. (A.7) is μ-independent and leaves, apart from a global rotation, the anomalous dimensions and the Wilson coefficients invariant. It, however, induces a finite renormalization of the physical operators. In order to restore the standard $\overline{\text{MS}}$ renormalization conditions these contributions must be removed by a change of scheme. Hence a ϵ-dependent linear transformation of the operator basis is equivalent to a global rotation and a change of scheme [39].

The finite renormalization corresponding to the above change of basis can be derived with simple algebra. Through $\mathcal{O}(\alpha_s^2)$ we find

$$\begin{aligned} \hat{Z}_{QQ}^{(1,0)} &= -\hat{R}\,\hat{Z}_{QE}^{\prime(1,1)}\hat{U}\hat{R}^{-1}\,, \\ \hat{Z}_{QQ}^{(2,0)} &= -\hat{R}\left(\hat{Z}_{QE}^{\prime(2,1)}\hat{U} + \hat{Z}_{QE}^{\prime(2,2)}\hat{V} - \frac{1}{2}\hat{Z}_{QE}^{\prime(1,1)}\hat{V}\hat{\gamma}^{\prime(0)}\right)\hat{R}^{-1}\,, \end{aligned} \tag{A.9}$$

where

$$\hat{Z}_{QE}^{\prime(2,2)} = \frac{1}{2}\left(\hat{Z}_{QE}^{\prime(1,1)}\hat{Z}_{EE}^{\prime(1,1)} + \frac{1}{2}\hat{\gamma}^{\prime(0)}\hat{Z}_{QE}^{\prime(1,1)} - \beta_0\hat{Z}_{QE}^{\prime(1,1)}\right). \tag{A.10}$$

As always, the matrix $\hat{M}$ encoding the rotation of evanescent operators does not affect the residual finite renormalization. Eqs. (A.9) and (A.10) agree with the NLO formulas of [29, 38] and generalize the NNLO formulas of [39].

The only feature which has not been discussed in the literature before is the appearance of the ϵ^2-dependent transformation characterized by $\hat{V}$ in Eq. (A.7). It induces a finite $\mathcal{O}(\alpha_s^2)$ renormalization described by the second and third term in the second line of Eqs. (A.9). The former term is analogous to the first line of Eqs. (A.9). The latter term stems from a ϵ-dependent $\mathcal{O}(\alpha_s)$ renormalization. While the ϵ-dependent change of scheme removes the finite terms, it still leaves the anomalous dimensions and the Wilson coefficients invariant. Yet it induces a finite $\mathcal{O}(\alpha_s^2)$ renormalization. The transformation to the

standard $\overline{\rm MS}$ scheme definitions requires the removal of this finite term, which is achieved by the last term in the second line of Eqs. (A.9).

The matrices entering the above equations are found from one- and two-loop matrix elements of physical and evanescent operators in the "standard" basis. The $\mathcal{O}(\alpha_s)$ ADM takes the following form [38, 39, 42]

$$\hat{\gamma}'^{(0)} = \begin{pmatrix} -4 & \frac{8}{3} \\ 12 & 0 \end{pmatrix} . \tag{A.11}$$

For the $\mathcal{O}(\alpha_s)$ mixing into the evanescent operators one obtains [38, 39, 42]

$$\hat{Z}'^{(1,1)}_{QE} = \begin{pmatrix} \frac{5}{12} & \frac{2}{9} & 0 & 0 \\ 1 & 0 & 0 & 0 \end{pmatrix} , \qquad \hat{Z}'^{(1,1)}_{EE} = \begin{pmatrix} -7 & -\frac{4}{3} & \frac{5}{12} & \frac{2}{9} \\ -6 & 0 & 1 & 0 \\ 0 & 0 & \frac{13}{3} & -\frac{28}{9} \\ 0 & 0 & -14 & -\frac{64}{3} \end{pmatrix} . \tag{A.12}$$

At $\mathcal{O}(\alpha_s^2)$ only the mixing of physical into evanescent operators is needed. It is given by [39, 42]

$$\hat{Z}^{(2,1)}_{QE} = \begin{pmatrix} \frac{1531}{288} - \frac{5}{216} f & -\frac{1}{72} - \frac{1}{81} f & \frac{1}{384} & -\frac{35}{864} \\ \frac{119}{16} - \frac{1}{18} f & \frac{8}{9} & -\frac{35}{192} & -\frac{7}{72} \end{pmatrix} . \tag{A.13}$$

The general NNLO formulas relating the initial conditions of the Wilson coefficients and the ADM in two different schemes have been derived recently [39]. They read

$$\vec{C}(\mu_W) = \left(\hat{1} + \frac{\alpha_s(\mu_W)}{4\pi} \hat{Z}^{(1,0)}_{QQ} + \left(\frac{\alpha_s(\mu_W)}{4\pi} \right)^2 \hat{Z}^{(2,0)}_{QQ} \right)^T (\hat{R}^{-1})^T \vec{C}'(\mu_W) , \tag{A.14}$$

and

$$\begin{aligned} \hat{\gamma}^{(0)} &= \hat{R} \hat{\gamma}'^{(0)} \hat{R}^{-1} , \\ \hat{\gamma}^{(1)} &= \hat{R} \hat{\gamma}'^{(1)} \hat{R}^{-1} - \left[\hat{Z}^{(1,0)}_{QQ}, \hat{\gamma}^{(0)} \right] - 2\beta_0 \hat{Z}^{(1,0)}_{QQ} , \\ \hat{\gamma}^{(2)} &= \hat{R} \hat{\gamma}'^{(2)} \hat{R}^{-1} - \left[\hat{Z}^{(2,0)}_{QQ}, \hat{\gamma}^{(0)} \right] - \left[\hat{Z}^{(1,0)}_{QQ}, \hat{\gamma}^{(1)} \right] - \left[\hat{Z}^{(1,0)}_{QQ}, \hat{\gamma}^{(0)} \right] \hat{Z}^{(1,0)}_{QQ} \\ &\quad - 4\beta_0 \hat{Z}^{(2,0)}_{QQ} - 2\beta_1 \hat{Z}^{(1,0)}_{QQ} + 2\beta_0 \big(\hat{Z}^{(1,0)}_{QQ} \big)^2 . \end{aligned} \tag{A.15}$$

Eqs. (A.8) to (A.15) allow one to transform the results for the initial conditions of the Wilson coefficients of the current-current operators and their ADM in the "standard" basis to the basis used in this paper. This enables us to verify that the well-established NLO results [38, 39, 42] coincide, after the change of scheme, with the expressions presented in the second line of Eqs. (25) and (29). For what concerns the NNLO we confirm both the two-loop initial conditions of the Wilson coefficients [32] as well as the corresponding three-loop ADM [39].

References

[1] G. Buchalla and A. J. Buras, Phys. Lett. B **333**, 221 (1994) [arXiv:hep-ph/9405259] and Phys. Rev. D **54**, 6782 (1996) [arXiv:hep-ph/9607447].

[2] G. Isidori, Annales Henri Poincare **4**, S97 (2003) [arXiv:hep-ph/0301159]; in Proceedings of the 2nd Workshop on the CKM Unitarity Triangle, Durham, England, 2003, eConf **C0304052**, WG304 (2003) [arXiv:hep-ph/0307014] and references therein.

[3] A. J. Buras, F. Schwab and S. Uhlig, arXiv:hep-ph/0405132.

[4] W. J. Marciano and Z. Parsa, Phys. Rev. D **53**, 1 (1996).

[5] G. Ecker, A. Pich and E. de Rafael, Nucl. Phys. B **303**, 665 (1988); D. Rein and L. M. Sehgal, Phys. Rev. D **39**, 3325 (1989); J. S. Hagelin and L. S. Littenberg, Prog. Part. Nucl. Phys. **23**, 1 (1989); M. Lu and M. B. Wise, Phys. Lett. B **324**, 461 (1994) [arXiv:hep-ph/9401204]; C. Q. Geng, I. J. Hsu and Y. C. Lin, Phys. Rev. D **50**, 5744 (1994) [arXiv:hep-ph/9406313] and Phys. Lett. B **355**, 569 (1995) [arXiv:hep-ph/9506313]; S. Fajfer, Nuovo Cim. A **110**, 397 (1997) [arXiv:hep-ph/9602322]; A. F. Falk, A. Lewandowski and A. A. Petrov, Phys. Lett. B **505**, 107 (2001) [arXiv:hep-ph/0012099].

[6] G. Isidori, F. Mescia and C. Smith, Nucl. Phys. B **718**, 319 (2005) [arXiv:hep-ph/0503107].

[7] G. Isidori, G. Martinelli and P. Turchetti, arXiv:hep-lat/0506026.

[8] N. Cabibbo, Phys. Rev. Lett. **10**, 531 (1963); M. Kobayashi and T. Maskawa, Prog. Theor. Phys. **49**, 652 (1973).

[9] G. Buchalla and A. J. Buras, Nucl. Phys. B **412**, 106 (1994) [arXiv:hep-ph/9308272].

[10] G. Buchalla and A. J. Buras, Nucl. Phys. B **548**, 309 (1999) [arXiv:hep-ph/9901288].

[11] W. A. Bardeen, A. J. Buras, D. W. Duke and T. Muta, Phys. Rev. D **18**, 3998 (1978).

[12] G. Buchalla and A. J. Buras, Nucl. Phys. B **398**, 285 (1993) and B **400**, 225 (1993).

[13] M. Misiak and J. Urban, Phys. Lett. B **451**, 161 (1999) [arXiv:hep-ph/9901278].

[14] A. I. Vainshtein, V. I. Zakharov, V. A. Novikov and M. A. Shifman, Phys. Rev. D **16**, 223 (1977); J. R. Ellis and J. S. Hagelin, Nucl. Phys. B **217**, 189 (1983); C. Dib, I. Dunietz and F. J. Gilman, Mod. Phys. Lett. A **6**, 3573 (1991).

[15] A. J. Buras, M. Gorbahn, U. Haisch and U. Nierste, Phys. Rev. Lett. **95**, 261805 (2005) [arXiv:hep-ph/0508165].

[16] S. S. Chern and J. Simons, Annals Math. **99**, 48 (1974).

[17] S. A. Larin, Phys. Lett. B **303**, 113 (1993) [arXiv:hep-ph/9302240].

[18] S. L. Adler, Phys. Rev. **177**, 2426 (1969); J. S. Bell and R. Jackiw, Nuovo Cim. A **60**, 47 (1969).

[19] J. Charles *et al.* [CKMfitter Group], Eur. Phys. J. C **41**, 1 (2005), [arXiv:hep-ph/0406184] and August 1, 2005 update available at http://www.slac.stanford.edu/xorg/ckmfitter/ckm_results_summerEPS2005.html.

[20] M. Ciuchini *et al.*, JHEP **0107**, 013 (2001) [arXiv:hep-ph/0012308] and September 22, 2005 update available at http://utfit.roma1.infn.it/.

[21] J. F. Arguin *et al.* [The Tevatron Electroweak Working Group], arXiv:hep-ex/0507091.

[22] C. Bobeth, P. Gambino, M. Gorbahn and U. Haisch, JHEP **0404**, 071 (2004) [arXiv:hep-ph/0312090].

[23] G. Buchalla and A. J. Buras, Phys. Rev. D **57**, 216 (1998) [arXiv:hep-ph/9707243].

[24] S. Eidelman *et al.* [Particle Data Group], Phys. Lett. B **592** (2004) 1, and 2005 partial update for edition 2006 available at http://pdg.lbl.gov/.

[25] T. Inami and C. S. Lim, Prog. Theor. Phys. **65**, 297 (1981) [Erratum-ibid. **65**, 1772 (1981)]; G. Buchalla, A. J. Buras and M. K. Harlander, Nucl. Phys. B **349**, 1 (1991).

[26] K. Melnikov and T. van Ritbergen, Phys. Lett. B **482**, 99 (2000) [arXiv:hep-ph/9912391].

[27] A. J. Buras and P. H. Weisz, Nucl. Phys. B **333**, 66 (1990).

[28] M. J. Dugan and B. Grinstein, Phys. Lett. B **256**, 239 (1991).

[29] S. Herrlich and U. Nierste, Nucl. Phys. B **455**, 39 (1995) [arXiv:hep-ph/9412375].

[30] J. Collins, Renormalization, Cambridge University Press, New York 1984 and references therein.

[31] C. Greub and T. Hurth, Phys. Rev. D **56**, 2934 (1997) [arXiv:hep-ph/9703349]; A. J. Buras, A. Kwiatkowski and N. Pott, Nucl. Phys. B **517**, 353 (1998) [arXiv:hep-ph/9710336].

[32] C. Bobeth, M. Misiak and J. Urban, Nucl. Phys. B **574**, 291 (2000) [arXiv:hep-ph/9910220].

[33] P. Gambino and U. Haisch, JHEP **0110**, 020 (2001) [arXiv:hep-ph/0109058].

[34] M. Misiak and M. Steinhauser, Nucl. Phys. B **683**, 277 (2004) [arXiv:hep-ph/0401041].

[35] M. S. Chanowitz, M. Furman and I. Hinchliffe, Nucl. Phys. B **159**, 225 (1979).

[36] M. Ciuchini, E. Franco, G. Martinelli and L. Reina, Nucl. Phys. B **415**, 403 (1994) [arXiv:hep-ph/9304257].

[37] G. Altarelli, G. Curci, G. Martinelli and S. Petrarca, Nucl. Phys. B **187**, 461 (1981).

[38] K. G. Chetyrkin, M. Misiak and M. Münz, Nucl. Phys. B **520**, 279 (1998) [arXiv:hep-ph/9711280].

[39] M. Gorbahn and U. Haisch, Nucl. Phys. B **713**, 291 (2005) [arXiv:hep-ph/0411071].

[40] M. Misiak and M. Münz, Phys. Lett. B **344**, 308 (1995) [arXiv:hep-ph/9409454].

[41] K. G. Chetyrkin, M. Misiak and M. Münz, Nucl. Phys. B **518**, 473 (1998) [arXiv:hep-ph/9711266].

[42] P. Gambino, M. Gorbahn and U. Haisch, Nucl. Phys. B **673**, 238 (2003) [arXiv:hep-ph/0306079].

[43] D. J. Broadhurst, Eur. Phys. J. C **8**, 311 (1999) [arXiv:hep-th/9803091] and references therein.

[44] W. Wetzel, Nucl. Phys. B **196**, 259 (1982); W. Bernreuther and W. Wetzel, Nucl. Phys. B **197**, 228 (1982) [Erratum-ibid. B **513**, 758 (1998)]; W. Bernreuther, Annals Phys. **151**, 127 (1983) and Z. Phys. C **20** (1983) 331.

[45] S. A. Larin, T. van Ritbergen and J. A. M. Vermaseren, Nucl. Phys. B **438**, 278 (1995) [arXiv:hep-ph/9411260]; K. G. Chetyrkin, B. A. Kniehl and M. Steinhauser, Nucl. Phys. B **510**, 61 (1998) [arXiv:hep-ph/9708255].

[46] A. J. Buras, M. Jamin and M. E. Lautenbacher, Nucl. Phys. B **408**, 209 (1993) [arXiv:hep-ph/9303284].

[47] A. J. Buras, M. Jamin, M. E. Lautenbacher and P. H. Weisz, Nucl. Phys. B **370**, 69 (1992) [Addendum-ibid. B **375**, 501 (1992)].

[48] A. J. Buras, M. Jamin and P. H. Weisz, Nucl. Phys. B **347**, 491 (1990); S. Herrlich and U. Nierste, Nucl. Phys. B **419**, 292 (1994) [arXiv:hep-ph/9310311]; A. J. Buras, P. Gambino and U. Haisch, Nucl. Phys. B **570**, 117 (2000) [arXiv:hep-ph/9911250].

[49] G. 't Hooft and M. J. G. Veltman, Nucl. Phys. B **44**, 189 (1972); P. Breitenlohner and D. Maison, Commun. Math. Phys. **52**, 11 (1977), **52**, 39 (1977) and **52**, 55 (1977).

[50] W. Siegel, Phys. Lett. B **84**, 193 (1979).

[51] D. Stöckinger, JHEP **0503**, 076 (2005) [arXiv:hep-ph/0503129].

[52] L. F. Abbott, Nucl. Phys. B **185**, 189 (1981) and references therein.

[53] S. L. Adler and W. A. Bardeen, Phys. Rev. **182**, 1517 (1969).

[54] M. Bos, Nucl. Phys. B **404**, 215 (1993) [arXiv:hep-ph/9211319] and references therein.

[55] D. J. Gross and R. Jackiw, Phys. Rev. D **6**, 477 (1972); C. Bouchiat, J. Iliopoulos and P. Meyer, Phys. Lett. B **38** (1972) 519; C. P. Korthals Altes and M. Perrottet, Phys. Lett. B **39**, 546 (1972).

[56] T. L. Trueman, Phys. Lett. B **88**, 331 (1979).

[57] O. V. Tarasov, JINR-P2-82-900; O. V. Tarasov, A. A. Vladimirov and A. Y. Zharkov, Phys. Lett. B **93**, 429 (1980); S. A. Larin and J. A. M. Vermaseren, Phys. Lett. B **303**, 334 (1993) [arXiv:hep-ph/9302208].

[58] S. Herrlich and U. Nierste, Nucl. Phys. B **476**, 27 (1996) [arXiv:hep-ph/9604330].

[59] M. Beneke, T. Feldmann and D. Seidel, Nucl. Phys. B **612**, 25 (2001) [arXiv:hep-ph/0106067]; H. M. Asatrian, K. Bieri, C. Greub and M. Walker, Phys. Rev. D **69**, 074007 (2004) [arXiv:hep-ph/0312063].

[60] K. G. Chetyrkin, J. H. Kühn and M. Steinhauser, Comput. Phys. Commun. **133**, 43 (2000).

[61] J. H. Kühn and M. Steinhauser, Nucl. Phys. B **619**, 588 (2001) [Erratum-ibid. B **640**, 415 (2002)] [arXiv:hep-ph/0109084]; J. Rolf and S. Sint [ALPHA Collaboration], JHEP **12**, 007 (2002) [arXiv:hep-ph/0209255]; A. H. Hoang and M. Jamin, Phys. Lett. B **594**, 127 (2004) [arXiv:hep-ph/0403083]; O. Buchmüller and H. Flächer, arXiv:hep-ph/0507253; A. H. Hoang and A. V. Manohar, arXiv:hep-ph/0509195.

[62] T. Goto, N. Kitazawa, Y. Okada and M. Tanaka, Phys. Rev. D **53**, 6662 (1996) [arXiv:hep-ph/9506311]; A. G. Cohen, D. B. Kaplan, F. Lepeintre and A. E. Nelson, Phys. Rev. Lett. **78**, 2300 (1997) [arXiv:hep-ph/9610252]; Y. Grossman, Y. Nir and M. P. Worah, Phys. Lett. B **407**, 307 (1997) [arXiv:hep-ph/9704287]; G. Barenboim, G. Eyal and Y. Nir, Phys. Rev. Lett. **83**, 4486 (1999) [arXiv:hep-ph/9905397].

[63] M. Steinhauser, Comput. Phys. Commun. **134** (2001) 335 [arXiv:hep-ph/0009029].

[64] A. J. Buras, M. Jamin, M. E. Lautenbacher and P. H. Weisz, Nucl. Phys. B **400**, 37 (1993) [arXiv:hep-ph/9211304].